

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		100% STATE ROADWAY 0004 RURAL	100% STATE BRIDGE 0011 SN 093-0025
50300255	CONCRETE SUPERSTRUCTURE	CU YD	348.9		348.9
50300260	BRIDGE DECK GROOVING	SQ YD	923		923
50300280	CONCRETE ENCASEMENT	CU YD	12		12
50300300	PROTECTIVE COAT	SQ YD	1160		1160
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3978		3978
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	112120		112120
50800515	BAR SPLICERS	EACH	1018		1018
51201900	FURNISHING STEEL PILES HP14X89	FOOT	1320		1320
51202305	DRIVING PILES	FOOT	620		620
51203900	TEST PILE STEEL HP14X89	EACH	2		2
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	92		92
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\ps_work\pwsdot\staffennk\d0122332\07	4219-ehc-a00.dgn	DRAWN -	REVISED -			332	(12,B2)B-1	WABASH	68	5	
	PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -			CONTRACT NO. 74219					
Default	PLOT DATE = 8/12/2014	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.