

SUMMARY OF QUANTITIES - CONT

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE	
				RURAL	
				FAP 42 IL 13 : 127	FAP 42 IL 13 : 127
				ROADWAY 0004	SN 039-0009 0014
40600990	TEMPORARY RAMP	SQ YD	48	48	
40603090	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N90	TON	707	707	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	428	428	
40701916	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 3/4"	SQ YD	7938	7938	
44000100	PAVEMENT REMOVAL	SQ YD	3759	3759	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1988	1988	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	144	144	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	190	190	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2497	2497	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5714	5714	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	108	108	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2	
50105220	PIPE CULVERT REMOVAL	FOOT	119	119	

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES: SHEET 3 OF 8	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0:\p\work\p\vidot\1ef\usah\1\0196163\7019-shtr-cover-etc.dgn		DRAWN -	REVISED -			42	138-1	JACKSON	112	7
#MODELNAME#	PLOT SCALE = 1/8" = 1' / 1"	CHECKED -	REVISED -		SCALE:	SHEET 3 OF 8 SHEETS STA.		TO STA.		CONTRACT NO. 78215
	PLOT DATE = 8/18/2014	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				