

SUMMARY OF QUANTITIES

FAP 885 (IL 146)
100% STATE
3P RESURFACING
POPE COUNTY
CONSTRUCTION TYPE CODE 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	127,285
Z0034105	MATERIAL TRANSFER DEVICE	TON	23,838
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5mm FG, N90	TON	7980
40600990	TEMPORARY RAMP	SQ YD	225
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE C, N90	TON	15,858
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	188,482
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	422
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	18
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	148
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	129,333
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	1872.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4