

PAVEMENT MARKING SCHEDULE

LOCATION MP TO MP	LENGTH	LINE 4"			REMARKS
		SOLID WHITE	SKIP DASH YELLOW	SOLID YELLOW	
		FOOT	FOOT	FOOT	
WILLIAMSON COUNTY					
0 TO 1.63	8606	17213	2152		PASSING ZONE
WILLIAMSON COUNTY SUBTOTALS		17213	2152	0	
JOHNSON COUNTY					
1.63 TO 2.15	2746	5491	686		PASSING ZONE
2.15 TO 2.2	264	528	66	264	NO PASSING RIGHT
2.2 TO 2.35	792	1584	198		PASSING ZONE
2.35 TO 2.51	845	1690	211	845	NO PASSING LEFT
2.51 TO 3.7	6283	12566	1571		PASSING ZONE
3.7 TO 3.91	1109	2218	277	1109	NO PASSING RIGHT
3.91 TO 4.05	739	1478		1478	NO PASSING ZONE
JOHNSON COUNTY SUBTOTALS		25555	3009	3696	
TOTALS		42,768	5,161	3,696	
		51,625			

NOTE: MP 0.0 IS STATION 743+38

FILE NAME =	USER NAME = Stoverpg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.P. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\stoverpg\0383753\784	7-sht-plan.dgn	DRAWN -	REVISED -			BBI	34RS-6	*	13	10
	PLDT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: _____					
	PLDT DATE = 6/12/2014	DATE -	REVISED -		SHEET NO. ___ OF ___ SHEETS					
								CONTRACT NO. 78417		
ILLINOIS FED. AID PROJECT										