

# SUMMARY OF QUANTITIES

FUNDING:	100% STATE
LOCATION:	RURAL
ROUTE:	IL 145 (FAP 132)
	POPE

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	RESURFACING
				0005
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,357	1,357
<del>40600300</del>	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>351</del>	<del>351</del>
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	9587	9587
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	894	894
40600990	TEMPORARY RAMP	SO YD	115	115
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	19479	19479
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	588	588
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	226859	226859
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	3353	3353
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	816	816
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	563	563
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	148	148
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3982	3982
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6