	CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE 80% FED. 20% STATE ROADWAY J000-2A	80% FED. 20% STATE ROADWAY I000-2A	IL. RTE. 22 & TELEGRAPH RD. 80% FED. / 10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & WAUKEGAN RD. 80% FED. 20% STATE TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & RIDGE RD./ TENNYSON LN. 80% FED. / 10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & RIDGE RD. 80% FED. / 13.3% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE INTERCONNECT Y031-1F	50% STATE 50% BANNOCKBURN SIDEWALK SFTY-1B	100% HIGHLAND PARK EMERGENCY PRE-EMPTION Y031-3D	100% BANNOCKBURN EMERGENCY PRE-EMPTION Y031-3D
	20101000	TEMPORARY FENCE	FOOT	2,010	2,010									
	20200100	EARTH EXCAVATION	CU YD	33,898	33,898									
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	21,789	21,789									
	20400800	FURNISHED EXCAVATION	CU YD	2,614	2,614									
	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,867	1,867									
	20800150	TRENCH BACKFILL	CU YD	10,694	10,694									
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7,100	7,100									
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	41,166	41,166									
*	21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	7,842	7,842									
*	25000210	SEEDING, CLASS 2A	ACRE	5.63	5.63									
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	777	777									
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	777	777									
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	777	777									
*	25100630	EROSION CONTROL BLANKET	SQ YD	27,249	27,249									
*	25200110	SODDING, SALT TOLERANT	SQ YD	21,759	21,759									
*	25200200	SUPPLEMENTAL WATERING	UNIT	1,110	1,110									
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	902	902									
	28000305	TEMPORARY DITCH CHECKS	FOOT	432	432									
	28000400	PERIMETER EROSION BARRIER	FOOT	5,024	5,024									
	28000510	INLET FILTERS	EACH	255	255									
	28100105	STONE RIPRAP, CLASS A3	SQ YD	54	54									
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	906	906									
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	8,028	2,447							5,581		
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1,581		1,581								
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	867		867								
	35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	543		543								
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4		0.4								
	40600300	AGGREGATE (PRIME COAT)	TON	1.8		1.8								
	X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,061		1,061								
	40600895	CONSTRUCTING TEST STRIP	EACH	1		1								

* SPECIALTY ITEMS

(SHEET 1 OF 10)

Rev

FILE NAME = W:\ILRTE22_2009 REVISIONS\CADD Sheets\0160860-sht-S00.dgn	USER NAME = $USER$	DESIGNED - LP	REVISED -
		DRAWN - LP	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - JP	REVISED -
	PLOT DATE = 5/16/2010	DATE - 05/14/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. ROUTE 22
SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 3 OF 232 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-4	LAKE	232	3

CONTRACT NO. 60860

ILLINOIS FED. AID PROJECT