SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE: 80% FED. 20% STATE ROADWAY J000-2A	80% FED. 20% STATE ROADWAY I000-2A	IL. RTE. 22 & TELEGRAPH RD. 80% FED./10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & WAUKEGAN RD. 20% STATE TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & RIDGE RD./ TENNYSON LN. 80% FED./10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & RIDGE RD. 80% FED./13.3% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE INTERCONNECT Y031-1F	50% STATE 50% BANNOCKBURN SIDEWALK SFTY-1B	100% HIGHLAND PARK EMERGENCY PRE-EMPTION Y031-3D	100% BANNOCKBURN EMERGENCY PRE-EMPTION Y031-3D
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,168		1,168								
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	115		115								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,073		448						625		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	77		77								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,559		2,559								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	235		235								
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	57,364	57,364									
42001300	PROTECTIVE COAT	SQ YD	73,289	73,289									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	35,896	2,545							33,351		
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1,037	474							563		
42400800	DETECTABLE WARNINGS	SQ FT	1,175	1,175									
44000100	PAVEMENT REMOVAL	SQ YD	44,221	44,221									
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	22,491		22,491								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,841	2,841									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	24,263	24,263									
44000600	SIDEWALK REMOVAL	SQ FT	13,015	13,015									
X4402805	ISLAND REMOVAL	SQ FT	973	973									
44003100	MEDIAN REMOVAL	SQ FT	98,660	98,660									
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	334		334								
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	80		80								
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	26		26								
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8,409	8,409									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	42	42									
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4									
50105220	PIPE CULVERT REMOVAL	FOOT	1,108	1,108									
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	14	14									
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	1	1									
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	19	19									
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	2	2									
54216190	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 12" RISER	EACH	9	9									

* SPECIALTY ITEMS

Rev.

FILE NAME = W:\ILRTE22_2009 REVISIONS\CADD Sheets\D160860-sht-SQQ.dgn	USER NAME = $USER$	DESIGNED - LP	REVISED -
		DRAWN - LP	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - JP	REVISED -
	PLOT DATE = 5/16/2010	DATE - 05/14/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. ROUTE 22
SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 4 OF 232 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-4	LAKE	232	4
		CONTRACT NO. 60860		
		ILLINOIS FED. AID PROJECT		