

PROPOSED PAVEMENT MARKING											
LOCATION STA. - STA.	POLYUREA PAVEMENT					THERMOPLASTIC PAVEMENT					RAISED REFLEC. MARKERS (EACH)
	MARKING LINE				LETTERS & SYMBOLS (SQ FT)	MARKING LINE				LETTERS & SYMBOLS (SQ FT)	
	4" (FT)	6" (FT)	12" (FT)	24" (FT)		4" (FT)	6" (FT)	12" (FT)	24" (FT)		
<b>IL. ROUTE 22</b>											
45+50.89 - 52+00	1067.22	618.9	212.5	17.7	109.2						54
52+00 - 67+00	660	961.7	188.6	76.5	109.2						74
67+00 - 82+00	650	1203.3	136.6	149.4	109.2						78
82+00 - 97+00	700	813.77	138.4	122.2	329.2						88
97+00 - 112+00	650	4358.4	654.5	458.2	668.4						104
112+00 - 127+00	120	201.3	0	0	36.4						19
127+00 - 142+00						140	98.4	0	0	36.4	20
142+00 - 157+00						650	377.6	357.6	302.9	72.8	73
157+00 - 172+00						720	247.6	126.7	0	72.8	82
172+00 - 174+82.92						120	0	0	0	0	12
<b>IL. ROUTE 43</b>											
315+61.61 - 326+00	280	506.2	0	48	231.6						40
330+00 - 337+52.22	310	478	0	24	170.4						42
<b>TOTAL</b>	<b>4437.22</b>	<b>9141.6</b>	<b>1330.5</b>	<b>896</b>	<b>2187.6</b>	<b>1630</b>	<b>1640.5</b>	<b>484.3</b>	<b>302.9</b>	<b>182</b>	<b>686</b>

COMBINATION CONCRETE CURB & GUTTER		
LOCATION STA. - STA.	TYPE	
	B-6.12 (FT)	B-6.24 (FT)
<b>IL. ROUTE 43</b>		
315+61.61 - 326+00		2118.47
330+00 - 337+52.22		2142.29
<b>IL. ROUTE 22</b>		
45+50.89 - 52+00		1263.93
52+00 - 67+00		4315.76
67+00 - 82+00		4149.77
82+00 - 97+00		5380.39
97+00 - 112+00	458.24	4030.57
112+00 - 127+00		1383.78
127+00 - 142+00		1499.84
142+00 - 157+00		3974.54
157+00 - 172+00		4231.22
172+00 - 174+82.92		783.51
<b>TOTAL</b>		<b>35274.00</b>

CONCRETE MEDIAN	
LOCATION STA. - STA.	TYPE
	SB-6.24 (SQ. YD)
<b>IL. ROUTE 43</b>	
315+61.61 - 326+00	1986.04
330+00 - 337+52.22	1459.83
<b>IL. ROUTE 22</b>	
45+50.89 - 52+00	1686.61
52+00 - 67+00	3955.16
67+00 - 82+00	4055.90
82+00 - 97+00	
97+00 - 112+00	
112+00 - 127+00	
127+00 - 142+00	
142+00 - 157+00	1132.56
157+00 - 172+00	1132.56
172+00 - 174+82.92	1459.83
<b>TOTAL</b>	<b>14408.7</b>

TEMPORARY PAVEMENT MARKING						
STAGE	LOCATION STA. - STA.	LINE SIZE				LETTERS & SYMBOLS (SQ FT)
		4" (FT)	6" (FT)	12" (FT)	24" (FT)	
STAGE 1	<b>IL. ROUTE 22</b>					
	45+50.89 - 52+00	300.00				
	52+00 - 67+00	3180.00				
	67+00 - 82+00	2580.00				
	82+00 - 97+00	4365.00				61.2
	97+00 - 112+00	4657.56	370.00			412.8
	112+00 - 127+00	870.00				
	127+00 - 142+00	3230.00	680.00	23.67		36.3
	142+00 - 157+00	1830.00	960.00	63.02		72.6
	157+00 - 172+00		90.00			
172+00 - 174+82.92		120.00				
STAGE 2	<b>IL. ROUTE 43</b>					
	315+61.61 - 326+00	1716.72	100.00			72.6
	330+00 - 337+52.22	2797.86	53.71			36.3
	<b>TOTAL</b>	<b>72,406</b>	<b>6,259</b>	<b>11,123</b>	<b>186</b>	<b>1,154</b>

WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III						
STAGE	LOCATION STA. - STA.	LINE SIZE				LETTERS & SYMBOLS (SQ FT)
		4" (FT)	6" (FT)	12" (FT)	24" (FT)	
STAGE 3	<b>IL. ROUTE 22</b>					
	45+50.89 - 52+00	2163.89	216.54	14.50		72.6
	52+00 - 67+00	3316.41	98.43	65.33	30.00	36.3
	67+00 - 82+00	4697.14	277.62	50.25		72.6
	82+00 - 97+00	3647.75		37.96		
	97+00 - 112+00	4315.74	760.04		66.00	437.7
	112+00 - 127+00	1442.38				
	127+00 - 142+00	1836.17	63.26			36.3
	142+00 - 157+00	4463.25	221.98	149.09		72.6
	157+00 - 172+00	2953.22	114.82			36.3
172+00 - 174+82.92	695.14					
STAGE 4	<b>IL. ROUTE 43</b>					
	315+61.61 - 326+00	2375.51	92.89	33.59	22.00	61.2
	330+00 - 337+52.22	3107.64	80.51	84.31		
	<b>IL. ROUTE 22</b>					
	45+50.89 - 52+00	1253.84	407.14			72.6
	52+00 - 67+00	2654.79	246.25			72.6
	67+00 - 82+00	2780.33	605.34			72.6
	82+00 - 97+00	2039.28	955.81			72.6
	97+00 - 112+00	1837.06	1803.17		110.00	560.1
	112+00 - 127+00	2240.78	98.21			36.3
127+00 - 142+00	1974.26	745.71			72.6	
142+00 - 157+00	1524.18	374.07			72.6	
157+00 - 172+00		349.48			36.3	
172+00 - 174+82.92		106.00				
STAGE 4	<b>IL. ROUTE 43</b>					
	315+61.61 - 326+00	1562.18	510.33		52.00	170.1
	330+00 - 337+52.22	2040.39	556.71		22.00	133.8
	<b>TOTAL</b>	<b>54,921</b>	<b>8,684</b>	<b>435</b>	<b>302</b>	<b>2,198</b>

POROUS GRANULAR EMBANKMENT, SUBGRADE			
STREET	LOCATION (STA. TO STA.)	THICKNESS	QUANTITY (CU YD)
IL RTE 22	FROM STA. 62+00 TO STA. 65+50 (FULL WIDTH OF THE ROADWAY AGGREGATE SUBGRADE)	6"	502
IL RTE 22	FROM STA. 80+00 RT TO STA. 87+00 RT (10 FOOT WIDE DITCH AREA)	12"	260 *
IL RTE 43	FROM STA. 328+00 TO STA. 330+00 (FULL WIDTH OF THE ROADWAY AGGREGATE SUBGRADE)	12"	1,105
<b>TOTAL:</b>			<b>1,867</b>

\* THE PGE SHOULD ONLY BE USED IF THE DITCH CAN NOT BE ADEQUATELY CLEANED AND DRIED PRIOR TO PLACEMENT OF EMBANKMENT.