

CODE #	ITEM	UNIT	90% FED./10% STATE TOTAL QUANTITY		CONSTRUCTION TYPE CODE				
					TRAFFIC SIGNALS	CHICAGO LIGHTING	IDOT LIGHTING	BRIDGE	SURVEILLANCE
				ROADWAY	Y031-1F	Y030-1E	Y030-1E	X271-2A	Y032-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	84	84					
20200100	EARTH EXCAVATION	CU YD	727	727					
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	263					263	
20800150	TRENCH BACKFILL	CU YD	368	368					
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	451	451					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	300	300					
25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50					
25000310	SEEDING, CLASS 4	ACRE	0.50	0.50					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	50	50					
25000520	SEEDING, CLASS 5	ACRE	0.50	0.50					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	50	50					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	50	50					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300					
25100630	EROSION CONTROL BLANKET	SQ YD	4107	4107					
28000400	PERIMETER EROSION BARRIER	FOOT	255	255					
28000510	INLET FILTERS	EACH	3	3					
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	104	104					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	499	499					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	16	16					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	5	5					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1.8	1.8					
40603395	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	10.3	10.3					
42001300	PROTECTIVE COAT	SQ YD	1039	1039					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	499	499					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1698	1698					
42400800	DETECTABLE WARNINGS	SQ FT	29	29					
44000100	PAVEMENT REMOVAL	SQ YD	450	450					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	123	123					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	13	13					
44000300	CURB REMOVAL	FOOT	3	3					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	445	445					
44000600	SIDEWALK REMOVAL	SQ FT	1605	1605					
Z0004552	APPROACH SLAB REMOVAL	SQ YD	593	593					
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	40	40					
44004250	PAVED SHOULDER REMOVAL	SQ YD	490	490					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	34	34					
48203053	HOT-MIX ASPHALT SHOULDERS, 14"	SQ YD	490	490					
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1					1	
50102400	CONCRETE REMOVAL	CU YD	213					213	
Z0003617	REMOVAL OF EXISTING SUB-STRUCTURE	EACH	1					1	
50200100	STRUCTURE EXCAVATION	CU YD	940					940	
50300225	CONCRETE STRUCTURES	CU YD	506.6					506.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	592.8					592.8	
50300260	BRIDGE DECK GROOVING	SQ YD	1355					1355	

• SPECIALTY ITEM
 •• NON-PARTICIPATING
 ••• 100% CITY OF CHICAGO

Rev. 9-2-10 Rev

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = #SCALE#	DRAWN -	REVISED -					94	0101.8B	COOK	139	3
	PLOT DATE = #DATE#	CHECKED -	REVISED -			SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.		CONTRACT NO. 60C18		ILLINOIS FED. AID PROJECT		