

CODE #	ITEM	UNIT	90% FED./10% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY 1000	TRAFFIC SIGNALS Y031-1E	CHICAGO LIGHTING Y030-1E	IDOT LIGHTING Y030-1E	BRIDGE X271-2A	SURVEILLANCE Y032-1E
50300300	PROTECTIVE COAT	SQ YD	1822					1822	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1					1	
50500505	STUD SHEAR CONNECTORS	EACH	5112					5112	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	183807					183807	
50800515	BAR SPLICERS	EACH	928					928	
50901730	BRIDGE FENCE RAILING	FOOT	422					422	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1313					1313	
51202305	DRIVING PILES	FOOT	1313					1313	
51203600	TEST PILE STEEL HP12X53	EACH	1					1	
50026407	TEMPORARY SHEET PILING	SQ FT	3257					3257	
51500100	NAME PLATES	EACH	1					1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	182					182	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24					24	
58106400	ADJUSTING WATER MAIN 8"	FOOT	53	53					
58700300	CONCRETE SEALER	SQ FT	3723					3723	
59000200	EPOXY CRACK INJECTION	FOOT	49					49	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	253					253	
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2	2					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6					
60500040	REMOVING MANHOLES	EACH	1	1					
60600605	CONCRETE CURB, TYPE B	FOOT	16	16					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	161	161					
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	130	130					
* 63301235	REMOVE AND REERECT STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	182	182					
63700255	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	243	243					
63700805	CONCRETE BARRIER TRANSITION	FOOT	100	100					
63700900	CONCRETE BARRIER BASE	FOOT	313	313					
64200105	SHOULDER RUMBLE STRIP	FOOT	2958	2958					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18					
67100100	MOBILIZATION	L SUM	1	1					
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	4	4					
70103817	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	10	10					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	992	992					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2962.5	2962.5					

- SPECIALTY ITEM
- NON-PARTICIPATING
- 100% CITY OF CHICAGO

Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#	PLOT SCALE = #SCALE#	DRAWN -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	94	0101.8B	COOK	139	4	
	PLOT DATE = #DATE#	CHECKED -	REVISED -				TO STA.						
		DATE -	REVISED -										CONTRACT NO. 60C18

ILLINOIS FED. AID PROJECT