

URBAN
90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	BRIDGE	RETAINING WALL	HWY LIGHTING
				1000 - 2A URBAN	X271 - 2A URBAN	Y007 URBAN	Y030-1E URBAN
** Z0033030	MAST ARM, STEEL, STREET LIGHTING, 12 FT.	EACH	6				6
** X0322700	FUSE, IN-LINE, 10 AMP	EACH	12				12
** X0322725	RACK, SECONDARY-AERIAL, 2-WIRE OR 3- WIRE	EACH	1				1
** 81700225	ELECTRIC CABLE IN CONDUIT, ^{(600V (EPR-TYPE RHW))} 2-1/C NO. 6	FOOT	960				960
** Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	10	10			
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	2		2		
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	7,721	3,751	3,970		
X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	3,240				3,240
** X0324901	REMOVE EXISTING STREET LIGHTING FOUNDATION	EACH	2				2
* X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	1,077	1,077			
** Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1			
* X7030104	WET ^(PAVEMENT MARKING) TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	14,819	14,819			
* X7030124	WET ^(PAVEMENT MARKING) TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	50	50			
* X7030105	WET ^(PAVEMENT MARKING) TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	2,520	2,520			
* X7030108	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 6 INCH	FOOT	1,170	1,170			
** X0326323	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	28				28
** X0326327	POLE, STEEL, ANCHOR BASE, 8-1/2" DIAMETER, 7-GAUGE, 32'-6"	EACH	4				4
** X0326361	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE, 7 FOOT	EACH	2				2
** X0329888	REMOVE EXISTING STREET LIGHTING EQUIPMENT	L SUM	1				1
* X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
** X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1				1
** X8210456	LUMINAIRE, STREET LIGHTING, ^(HIGH PRESSURE SODIUM) VAPOR, 400 WATT, 240 VOLT, ARTERIAL, SEMI-CUTOFF	EACH	6				6
** X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	1,150	1,150			
** X0327035	WIRE AERIAL 1/C NO. 6	FOOT	220				220

** Specialty Items

Rev.