



CONSTRUCTION NOTES:

- ① THE CONTRACTOR SHALL DISCONNECT AND REMOVE EACH UNINTERRUPTIBLE POWER SUPPLY (UPS) CABINET AND ALL ASSOCIATED ITEMS NEEDED TO REINSTALL TO EACH NEW CONTROLLER CABINET. THE COST TO REINSTALL EACH OF THE UPS CABINETS WILL BE INCLUDED IN THE COST OF THE NEW CONTROLLER AND CABINET.
- ② THE CONTRACTOR SHALL REMOVE AND RELOCATE ALL THE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM PHASING UNITS FROM EACH OF THE EXISTING CONTROLLER CABINETS AND REINSTALL TO EACH OF THE NEW CABINETS. THE COST WILL BE INCLUDED IN THE COST OF THE NEW CONTROLLERS AND CABINETS.

THE CONTRACTOR SHALL INSTALL THE NEW SERVICE CABINET AND CONNECT TO THE EXISTING CONDUIT WITH A 1 1/2" REDUCER COUPLING. THE NEW SERVICE CABLE WILL THEN BE INSTALL AND THE EXISTING SERVICE CABLE REMOVED.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME =	USER NAME = kanthapxaybo	DESIGNED - SN/BK/JE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC SIGNAL MODIFICATION PLAN LAWRENCE AVE AT DES PLAINES RIVER RD.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cc:\pw_work\pwide\kanthapxaybo\d011261	traffic_legend.v8.dgn	DRAWN - SN/BK	REVISED -			1362	2009 102 N	COOK	17	13	
PLOT SCALE = 20.0000' / IN.	CHECKED - JE	REVISED -	REVISED -			CONTRACT NO. 60165					
PLOT DATE = 6/25/2010	DATE - 06/25/2010	REVISED -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

07:39:15 06/17/2010