



INTERCONNECT SCHEDULE OF QUANTITIES

QUANTITY	UNIT	ITEM
812	FOOT	CONDUIT IN TRENCH 2" DIA., GALVANIZED STEEL
1127	FOOT	CONDUIT PUSHED 2" DIA., GALVANIZED STEEL
5	EACH	HANDHOLE
812	FOOT	TRENCH AND BACKFILL FOR ELECTRICAL WORK
1	EACH	MASTER CONTROLLER
4	EACH	DRILL EXISTING HANDHOLE
3,530	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C
1	EACH	OPTIMIZE TRAFFIC SIGNAL SYSTEM
3,530	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F

FILE NAME =	USER NAME = kentaphixaybc	DESIGNED - SN/BK/JE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INTERCONNECT SCHEMATIC PLAN LAWRENCE AVE. FROM 25TH AVE. TO DES PLAINES RIVER RD.			F.A.U. RTE. 1362	SECTION 2009-102N	COUNTY COOK	TOTAL SHEETS 17	SHEET NO. 17	
or\p\work\p\dot\kentaphixaybc\d011261	tr\of\ic\legend.v8.dgn	DRAWN - SN/BK	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60165
	PLOT SCALE = 20,0000 ' / IN.	CHECKED - JE	REVISED -										
	PLOT DATE = 6/25/2010	DATE - 06/25/2010	REVISED -										

: 07:39:17 06/17/2010