

PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY
STATION TO STATION	(SQ FT)
87+81 TO 115+00	3529
TOTAL	3529

RAISED REFLECTIVE  
PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY
STATION TO STATION	(EACH)
97+76.50 TO 102+72.44	82
TOTAL	82

TEMPORARY INFORMATION SIGNING

LOCATION	QUANTITY
STATION TO STATION	(SQ FT)
JOBSITE	115
TOTAL	115

WET REFLECTIVE  
TEMPORARY TAPE, TYPE III 4"

LOCATION	QUANTITY
STATION	(FOOT)
WHITE	
STAGE 1	
87+81 TO 95+07 LT/RT	782
95+42 TO 102+85 LT/RT	837
103+35 TO 110+41 LT/RT	751
STAGE 2	
92+64 TO 103+10 LT/RT	1096
103+55 TO 104+81 LT/RT	230
105+06 TO 108+74 RT	392
109+16 TO 110+96 RT	185
SUBTOTAL =	4273
YELLOW	
SOLID YELLOW	
STAGE 1	
88+64 TO 93+81 LT/RT	517
90+45 TO 93+81 LT	336
104+60 TO 115+00 LT/RT	1040
104+60 TO 115+00 LT	1040
STAGE 2	
88+00 TO 94+82 RT	738
91+87 TO 94+82 LT/RT	295
104+67 TO 110+96 LT/RT	629
104+67 TO 110+96 LT/RT	629
DOUBLE YELLOW	
STAGE 1	
93+81 TO 94+65 LT	168
95+65 TO 102+38 LT	1346
103+75 TO 104+60 LT	170
STAGE 2	
95+66 TO 102+71 RT	1410
103+77 TO 104+67 RT	180
SUBTOTAL =	8498
TOTAL	12771

WET REFLECTIVE  
TEMPORARY TAPE, TYPE III, 24"

LOCATION	QUANTITY
STATION	(FOOT)
SOLID WHITE	
STAGE 1	
94+64 LT	12
95+67 LT	12
102+37 LT	12
103+76 LT	12
STAGE 2	
94+81 RT	12
95+67 RT	12
102+70 RT	12
103+78 RT	12
TOTAL	96

TEMPORARY ACCESS (COMMERCIAL ENTRANCE)

LOCATION	QUANTITY
STATION	(EACH)
98+29 RT	1
TOTAL	1

AGGREGATE SUBGRADE 12"

LOCATION	QUANTITY
STATION	OFFSET (SQ YD)
97+76.50 TO 99+28.28	LT/RT 1276.1
100+71.88 TO 102+22.50	LT/RT 1237.4
TOTAL	2514

CONSTRUCTION LAYOUT

LOCATION	QUANTITY
JOBSITE	(L SUM)
JOBSITE	1
TOTAL	1

IMPACT ATTENUATORS, TEMPORARY  
(FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	QUANTITY
STATION	(EACH)
STAGE 1	4
TOTAL	4

IMPACT ATTENUATORS, RELOCATE  
(FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	QUANTITY
STATION	(EACH)
STAGE 2	2
TOTAL	2