

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL @ SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ARTERIAL ROAD INFORMATION SIGN

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

ſ	FILE NAME =	USER NAME = \$USER\$	DESIGNED -	SEW	REVISED -	STATE OF ILLINOIS	DISTRICT 1 STANDARDS IL ROUTE 62 (ALGONQUIN ROAD) OVER SALT CREEK			F.A.P.	SECTION	COUNTY	TOTAL SHEET		
si	FILEL\$		DRAWN -	SEW	REVISED -					339	116-Y-2-BR-1	COOK	74 70		
		PLOT SCALE = \$SCALE\$	CHECKED ~	FML	REVISED -	DEPARTMENT OF TRANSPORTATION	IL N	OUTE OZ JALGUNGUIN NO	AD) UVEN SAL			TC-22		CONTRACT NO. 60J00	
L		PLOT DATE = \$DATE\$	DATE -	2/2010 REVISED -		SCALE: N.T.S.	SHEET NO. 11 OF 12 SHEETS	STA.	TO STA.	FED. ROA	D DIST. NO. ILLINOIS FED.	AID PROJECT			