

SUMMARY OF QUANTITIES			100% STATE			SUMMARY OF QUANTITIES			100% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BOX CULVERT X028-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BOX CULVERT X028-2A
51500100	NAME PLATES	EACH	1		1	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16	
54003000	CONCRETE BOX CULVERTS	CU YD	59		59	70400100	TEMPORARY CONCRETE BARRIER	FOOT	60	60	
54010808	PRECAST CONCRETE BOX CULVERTS 8'X8'	FOOT	133		133	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1120	1120	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	12	4
550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	54	54		* 78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	62		62	* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
60109580	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	80		80	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	12	4
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1		Z0030850	TEMPORARY INFORMATIONAL SIGNING	SQ FT	52	52	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	139	139		X0322641	TEMPORARY CLEAR WATER DIVERSION	L SUM	1		1
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	20		20	Z0023602	GRANULAR CULVERT BACKFILL	CU YD	1687		1687
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		XX006066	SIGN TO BE RELOCATED	EACH	2	2	
* Z0029310	GUARD RAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	12		12	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	232		232
63200310	GUARD RAIL REMOVAL	FOOT	138	138		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* 66400505	CHAIN LINK FENCE, 8'	FOOT	94	73	21	* Z0064800	SELECTIVE CLEARING	UNIT	1	1	
66410300	CHAIN LINK FENCE REMOVAL	FOOT	113	99	14						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5							
67100100	MOBILIZATION	L SUM	1	1							
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1							
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30							

* SPECIALTY ITEMS

LONCO INC.
CONSULTING ENGINEERS
1560 WALL ST. SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - SLV	REVISED -
DATE - 06/25/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
WEST RIVER ROAD OVER UNNAMED TRIBUTARY (0.1 MI N OF IL RT 113)**

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. 81+40 TO STA. 84+20

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0327	112 T-2	WILL	22	4
D-91-198-10			CONTRACT NO. 60J17	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev