

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 1000	100% CITY 50% STATE 1000				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 1000	100% CITY 50% STATE 1000			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	60	60					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
25200110	SODDING, SALT TOLERANT	SO YD	60	60					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4309	4309				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	372	372				
40600300	AGGREGATE (PRIME COAT)	TON	143	143					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8085	8085				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	54	54					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5400	5400				
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1414	1414					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	147	147				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	53	53				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	735	735					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	498	498				
40601005	HOT MIX ASPHALT REPLACEMENT OVER PATCHES	TON	421	421					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	8351	8351				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3606	3606					78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	372	372				
42001300	PROTECTIVE COAT	SO YD	200	200					78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8085	8085				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	25	25					78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5400	5400				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1125	1125					78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	147	147				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	34,286	34286					78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	53	53				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	25	25					78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	498	498				
44000600	SIDEWALK REMOVAL	SO FT	1125	1125					78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	359	359				
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	900	900					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	285	285				
44002217	HOT MIX ASPHALT REMOVAL OVER PATCHES, 1 1/4"	SO YD	1770	1770					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	884	884					Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	368	368					⊙ Z0076400	TRAINERS	HOURL	500	500				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	221	221					44000156	HOT MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	2507	2507				
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	800	800					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	194	194				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	92	92													
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5													
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													

• DENOTES SPECIALTY ITEM
Δ Non-participating
⊙ Y080