

# SUMMARY OF QUANTITIES

CONTRACT NO. 63348

CODE NO	ITEM	UNIT	TOTAL QUANTITY
			CONSTRUCTION CODE 1000
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	30
<del>20042002</del>	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	30
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	560
25000110	SEEDING, CLASS 1A	ACRE	0.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18
35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	200
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3421
40600300	AGGREGATE (PRIME COAT)	TON	51
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10
<del>40600826</del>	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	958
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	547
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	22
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1676
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5462
42400800	DETECTABLE WARNINGS	SQ FT	48
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	17106
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	200
44000600	SIDEWALK REMOVAL	SQ FT	5462
<del>20004542</del>	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2208
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	25

CODE NO	ITEM	UNIT	TOTAL QUANTITY
			CONSTRUCTION CODE 1000
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	50
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	200
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60262700	INLETS TO BE RECONSTRUCTED	EACH	2
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	500
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	104
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1300
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3930
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1556
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	932
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	220
88600100	DETECTOR LOOP, TYPE I	FOOT	562

\* DENOTES SPECIALTY ITEM(S)

VILLAGE OF WOODRIDGE PUBLIC WORKS  
 1 Plaza Drive, Woodridge IL 60517 (630) 719-4753  
**WOODRIDGE DRIVE  
 REHABILITATION PROJECT**  
**SUMMARY OF QUANTITIES**  
 DRAWN BY: AF CHECKED BY: SM