

Specialty Item	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY			SIDEWALK		LIGHTING		WATER MAIN & SANITARY SEWER
						70% STP 30% LOCAL	80% CMAQ 20% LOCAL	WASHINGTON STREET 100% LOCAL	80% CMAQ 20% LOCAL	100% LOCAL	70% STP 30% LOCAL	100% LOCAL	100% LOCAL
						I000-2A	I000-2A	I000-2A	SFTY -1B	SFTY-1B	Y030-1E	Y030-1E	Y060
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	25	25							
		60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	17	16		1					
		60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13	13							
	*	60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12								12
	*	60228140	MANHOLES, SANITARY, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2								2
	*	60249120	VALVE VAULTS, 5'-DIAMETER	EACH	1								1
		60255500	MANHOLES TO BE ADJUSTED	EACH	18	18							
	*	60266500	VALVE VAULTS TO BE REMOVED	EACH	1								1
		60500040	REMOVING MANHOLES	EACH	5	5							
		60500050	REMOVING CATCH BASINS	EACH	4	4							
		60500060	REMOVING INLETS	EACH	42	42							
		60600605	CONCRETE CURB, TYPE B	FOOT	434	434							
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	10575	10556		19					
X		66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	376	376							
X		66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1							
X		66900510	BETX-PNAS SOIL ANALYSIS	EACH	2	2							
X		66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4							
X		66900560	TCLP VOCS-SVOCs/PH/FLASH POINT/PAINT FILTER SOIL ANALYSIS	EACH	2	2							
X		66900610	ARSENIC AND PH SOIL ANALYSIS	EACH	2	2							
X		66901000	BACKFILL PLUGS	CU YD	18	18							
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12							
		67100100	MOBILIZATION	L SUM	1	1							
	*	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1							
	*	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1							
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12							
		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7892	7892							
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11630	11630							
		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	294	294							
		70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2209	2209							
		70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	32	32							



FILE NAME = 003-007_650soq01.dgn
 USER NAME = USER:3830
 PLOT SCALE = 1:1
 PLOT DATE = 7/2/2010

DESIGNED - M.W.	REVISED -
DRAWN - E.D.	REVISED -
CHECKED -	REVISED -
DATE - 9/23/2009	REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

SUMMARY OF QUANTITIES

SCALE: AS NOTED SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A. U. RTE. 2652	SECTION 00-00070-00-PV	COUNTY DuPAGE	TOTAL SHEETS 160	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63379	