

Specialty Item	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY			SIDEWALK		LIGHTING		WATER MAIN & SANITARY SEWER
						70% STP 30% LOCAL	80% CMAQ 20% LOCAL	WASHINGTON STREET 100% LOCAL	80% CMAQ 20% LOCAL	100% LOCAL	70% STP 30% LOCAL	100% LOCAL	100% LOCAL
						I000-2A	I000-2A	I000-2A	SFTY-1B	SFTY-1B	Y030-1E	Y030-1E	Y060
		70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	11	11							
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	591	591							
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	601	601							
X		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	272	272							
X		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5543	5543							
X		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1868	1868							
X		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	179	179							
X		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	304	304							
*		78200530	BARRIER WALL MARKERS, TYPE C	EACH	96	96							
		78300100	PAVEMENT MARKING REMOVAL	SQ FT	224	224							
X		80400100	ELECTRIC SERVICE INSTALLATION	EACH	1						1		
X	*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1						1		
X		81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	2319						2319		
X		81400100	HANDHOLE	EACH	15						15		
X		81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	400						400		
X		81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	316						316		
X		81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2631						2631		
X		81603110	UNIT DUCT, 600V, 4-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	3258						3258		
X		81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	150						150		
X		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6862						6862		
X		82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	26							26	
X	*	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1						1		
X		83006300	LIGHT POLE, ALUMINUM, 30 FT. M.H., 8 FT. MAST ARM	EACH	26							26	
X		83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	360						360		
X		84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	25						25		
X		88600100	DETECTOR LOOP, TYPE I	FOOT	444	444							
X	*	89502380	REMOVE EXISTING HANDHOLE	EACH	8						8		
X		A2004520	TREE, GINKGO BILOBA PRINCETON SENTRY (PRINCETON SENTRY GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	17		17						
X		B2005720	TREE, PYRUS CALLERYANA CHANTICLEER CHANTICLEER CALLERY PEAR), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	16		16						
*		Z0001510	ENGINEERED BARRIER	SQ YD	144	144							



FILE NAME = 003-007\_650soq01.dgn  
 USER NAME = USER3830  
 PLOT SCALE = 1:1  
 PLOT DATE = 7/15/2010

DESIGNED - M.W.	REVISED -
DRAWN - E.D.	REVISED -
CHECKED -	REVISED -
DATE - 9/23/2009	REVISED -

**VILLAGE OF VILLA PARK, ILLINOIS**

**SUMMARY OF QUANTITIES**

SCALE: AS NOTED SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00070-00-PV	DuPAGE	160	6
CONTRACT NO. 63379				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				