

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION				
							20200100	20201200	20700420	20400800
							CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
<b>STAGE 1</b>										
66+16.00	0	0	0	0	0	0				
66+23.40	3	3	1	0	0	2				
66+27.30	2	1	1	0	0	1				
66+50.00	9	8	2	0	0	6				
66+73.40	10	8	2	0	0	6				
66+81.98	4	3	1	0	0	2				
67+00.00	8	6	0	0	0	6				
67+03.66	2	1	0	0	0	1				
67+22.32	7	6	2	0	0	4				
67+50.00	8	7	3	0	0	4				
67+72.50	5	4	3	0	0	1				
67+78.30	1	1	1	0	0	0				
68+00.00	5	4	1	0	0	3				
68+42.34	10	9	1	0	0	8				
68+50.00	2	2	0	0	0	2				
68+62.03	4	3	1	0	0	2				
69+00.00	15	13	4	0	0	8				
69+13.23	6	5	1	0	0	5				
69+48.59	18	15	2	0	0	14				
69+50.00	1	1	0	0	0	1				
69+63.48	7	6	1	0	0	5				
70+00.00	20	17	3	0	0	14				
70+11.21	6	5	1	0	0	4				
70+39.02	15	13	2	0	0	11				
70+50.00	6	5	0	0	0	5				
70+63.17	7	6	1	0	0	5				
70+92.82	15	13	3	0	0	10				
71+00.00	4	3	0	0	0	3				
71+13.33	6	5	1	0	0	4				
71+50.00	16	14	3	0	0	11				
71+54.00	2	1	0	0	0	1				
71+62.92	4	3	1	0	0	2				
72+00.00	14	12	4	0	0	8				
72+09.43	3	3	1	0	0	2				
72+17.83	3	2	1	0	0	1				
72+50.00	11	10	3	0	0	7				
72+63.67	5	4	0	0	0	4				
72+72.34	3	3	1	0	0	2				
73+00.00	10	9	2	0	0	6				
73+18.58	7	6	1	0	0	5				
73+22.33	1	1	1	0	0	1				
73+50.00	12	10	2	0	0	8				
73+73.19	11	10	1	0	0	8				
74+00.00	15	12	2	0	0	11				
74+23.57	14	12	0	0	0	12				
74+30.59	4	3	0	0	0	3				
74+50.00	12	10	1	0	0	9				
74+79.27	18	16	0	0	0	16				
74+93.52	9	7	0	0	0	7				
75+00.00	4	3	0	0	0	3				
75+29.94	15	12	2	0	0	11				
75+37.74	3	3	1	0	0	2				

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION				
							20200100	20201200	20700420	20400800
							CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
75+50.00	5	4	0	0	0	4				
75+80.23	9	7	3	0	0	5				
76+00.00	5	4	2	0	0	2				
76+37.90	9	8	4	0	0	4				
76+39.95	1	0	0	0	0	0				
76+50.00	4	4	1	0	0	3				
76+65.86	31	26	1	0	0	26				
76+94.26	51	44	1	0	0	43				
77+00.00	2	1	0	0	0	1				
77+50.00	16	13	0	0	0	13				
77+98.88	15	13	0	0	0	13				
78+00.00	0	0	0	0	0	0				
78+50.00	16	13	4	0	0	9				
78+52.95	1	1	0	0	0	0				
78+62.61	3	2	2	0	0	1				
79+00.00	9	8	6	0	0	2				
79+02.60	1	1	0	0	0	0				
79+06.59	1	1	1	0	0	0				
79+46.57	12	11	3	0	0	8				
79+50.00	1	1	0	0	0	1				
79+70.54	6	5	2	0	0	4				
80+00.00	7	6	2	0	0	3				
80+04.46	1	1	0	0	0	1				
80+50.00	7	6	0	0	0	6				
80+71.74	3	2	3	0	0	0				
80+76.83	1	1	1	0	0	-1				
81+00.00	3	2	2	0	0	0				
81+22.31	2	2	3	0	0	-1				
81+50.00	3	2	3	0	0	-1				
81+63.31	1	1	0	0	0	1				
81+79.82	2	2	2	0	0	0				
82+00.00	2	2	2	0	0	0				
82+19.68	2	1	0	0	0	1				
82+50.00	2	2	1	0	0	1				
82+61.97	1	1	1	0	0	0				
82+71.43	0	0	1	0	0	-1				
83+00.00	1	1	3	0	0	-2				
83+21.29	1	1	2	0	0	-1				
83+27.09	0	0	1	0	0	-1				
83+50.00	2	2	3	0	0	-1				
83+83.02	3	2	4	0	0	-1				
83+89.37	0	0	1	0	0	-1				
84+00.00	1	1	1	0	0	0				
84+37.49	3	3	4	0	0	-1				
84+50.00	1	1	1	0	0	0				
84+54.37	0	0	0	0	0	0				
85+00.00	5	4	0	0	0	4				
85+32.23	3	2	4	0	0	-1				
85+50.00	1	1	2	0	0	-1				
85+88.53	5	4	4	0	0	0				
85+97.47	1	1	2	0	0	-1				
86+00.00	0	0	1	0	0	0				
86+50.00	6	5	10	0	0	-5				



FILE NAME = 018-015\_650sched01.dgn

USER NAME = #USER#	DESIGNED - J.G.	REVISED -
PLOT SCALE = 1:1	DRAWN - E.D.	REVISED -
PLOT DATE = 6/15/2010	CHECKED -	REVISED -
	DATE - 9/23/2009	REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

SCHEDULE OF QUANTITIES

SCALE: NO SCALE SHEET NO. 1 OF 6 SHEETS STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00070-00-PV	DUPAGE	160	10
CONTRACT NO. 63379				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				