

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
	20200100			20201200	20700420	20400800
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
86+50.25	0	0	0	0	0	0
87+00.00	6	5	0	0	0	5
87+29.89	2	2	0	0	0	2
87+50.00	1	1	0	0	0	1
87+92.40	5	4	5	0	0	-1
87+95.61	0	0	1	0	0	0
88+00.00	1	1	1	0	0	-1
88+17.84	3	3	2	0	0	0
88+49.37	4	4	2	0	0	2
88+50.00	0	0	0	0	0	0
89+00.00	3	3	3	0	0	-1
89+50.00	3	2	1	0	0	1
89+69.83	2	2	1	0	0	0
89+98.31	7	6	1	0	0	5
90+00.00	1	1	0	0	0	1
90+23.35	6	5	0	0	0	4
90+26.61	0	0	0	0	0	0
90+50.00	1	1	2	0	0	-1
91+00.00	3	2	2	0	0	0
91+02.91	0	0	0	0	0	0
91+17.09	0	0	2	0	0	-2
91+50.00	1	1	8	0	0	-7
91+87.36	2	2	8	0	0	-6
92+00.00	1	1	3	0	0	-2
92+28.92	1	1	12	0	0	-12
92+50.00	0	0	10	0	0	-9
92+86.37	1	1	17	0	0	-16
93+00.00	0	0	6	0	0	-6
93+32.33	1	1	9	0	0	-8
93+50.00	0	0	6	0	0	-6
93+56.67	0	0	3	0	0	-3
93+87.60	1	1	11	0	0	-11
94+00.00	0	0	3	0	0	-2
94+09.47	0	0	4	0	0	-3
94+34.18	0	0	9	0	0	-8
94+50.00	0	0	5	0	0	-5
94+84.04	1	0	11	0	0	-10
95+00.00	0	0	2	0	0	-2
95+12.23	0	0	3	0	0	-3
95+50.00	1	1	8	0	0	-7
95+63.28	0	0	2	0	0	-2
95+74.21	1	0	1	0	0	-1
96+00.00	2	2	0	0	0	2
96+23.86	2	2	3	0	0	-1
96+50.00	2	2	3	0	0	-1
97+00.00	6	5	0	0	0	5
97+26.31	4	3	2	0	0	1
97+47.46	3	3	4	0	0	-1
97+50.00	0	0	0	0	0	0
98+00.00	10	9	5	0	0	4
98+41.50	11	9	0	0	0	9
98+50.00	2	2	0	0	0	2
98+61.80	3	3	1	0	0	2

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
	20200100			20201200	20700420	20400800
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
98+76.58	4	3	2	0	0	1
98+83.98	2	2	1	0	0	1
99+00.00	5	4	2	0	0	3
99+35.21	13	11	4	0	0	7
99+50.00	6	5	2	0	0	4
100+00.00	0	0	0	27	4	0
100+50.00	0	0	0	32	9	0
101+00.00	0	0	0	54	32	0
101+05.69	0	0	0	8	5	0
101+10.90	0	0	0	8	5	0
101+50.00	0	0	7	48	25	-7
101+90.82	0	0	8	28	8	-8
102+00.00	0	0	2	6	2	-2
102+50.00	0	0	10	42	9	-10
102+57.03	0	0	0	7	1	0
103+00.00	0	0	0	47	4	0
103+45.29	0	0	0	52	4	0
103+50.00	0	0	0	5	1	0
104+00.00	0	0	1	54	4	-1
104+50.00	64	55	1	0	0	54
104+55.98	8	7	0	0	0	7
105+00.00	43	36	8	0	0	28
105+50.00	38	32	11	0	0	21
105+69.10	17	14	1	0	0	13
106+00.00	31	26	1	0	0	26
106+50.00	43	37	12	0	0	25
106+69.88	0	0	9	15	0	-9
107+00.00	0	0	11	21	1	-11
107+50.00	0	0	9	40	1	-9
107+50.50	0	0	0	1	0	0
107+93.06	0	0	0	44	0	0
108+00.00	0	0	0	7	0	0
108+30.43	0	0	0	30	0	0
108+50.00	0	0	0	19	0	0
109+00.00	36	30	10	0	0	20
109+46.68	73	62	9	0	0	53
109+50.00	8	7	2	0	0	5
110+00.00	56	47	41	0	0	7
110+50.00	0	0	31	0	0	-31
110+87.05	1	1	32	0	0	-32
110+94.12	0	0	8	0	0	-8
111+00.00	0	0	7	0	0	-7
111+35.53	1	1	36	0	0	-35
111+50.00	1	0	12	0	0	-11
112+00.00	3	3	25	0	0	-23
112+32.91	4	3	7	0	0	-4
112+50.00	2	2	2	0	0	0
112+52.59	0	0	0	0	0	0
113+00.00	5	4	11	0	0	-6
113+22.37	2	1	10	0	0	-9
113+50.00	2	2	17	0	0	-15
113+74.29	1	1	17	0	0	-16
114+00.00	1	0	17	0	0	-16



FILE NAME = 010-015_650sched01.dgn	USER NAME = \$USER\$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

SCHEDULE OF QUANTITIES

SCALE: NO SCALE SHEET NO. 2 OF 6 SHEETS STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE. 2652	SECTION 00-00070-00-PV	COUNTY	TOTAL SHEETS 160	SHEET NO. 11
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
CONTRACT NO. 63379				