PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | ALL NOTES ADDED | CADD FILE NAME | NOTE BOOK | NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | ALL NOTES ADDED | STRUCTURE NOTATNS CHKD | NOTE BOOK | NO. | BY | DATE

PROPOSED ℄ S VILLA AVE

PAVEMENT REMOVAL (TYP)

SIDEWALK REMOVAL (TYP)

PORTLAND CEMENT CONCRETE SIDEWALK, 5" (TYP) (SEE NOTE 5)

COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12 (TYP)

PROPOSED BUS STOP PAD (SEE NOTE 4)

RAISED CROSSWALK (SEE NOTE 3)

EX ROW

CRESCENT DR

E PARK BLVD

CENTRAL BLVD

S VILLA AVE

MATCHLINE STA 96+80

MATCHLINE STA 102+80

STA 98+79.35 PROPOSED ℄ S VILLA AVE= STA 401+22.41 ℄ CRESCENT DR

STA 101+13.56 PROPOSED ℄ S VILLA AVE= STA 501+44.01 ℄ PARK BLVD

STA 101+02.41 PROPOSED ℄ S VILLA AVE= STA 6+00.00 ℄ PARK BLVD

STA 102+59.22 PR ℄ S VILLA AVE= STA 703+24.59 ℄ CENTRAL BLVD

COMBINATION CURB AND GUTTER REMOVAL (TYP)

DRIVEWAY PAVEMENT REMOVAL (TYP)

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, 2" HOT-MIX ASPHALT BASE COURSE, 6" (TYP)

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6" (TYP)

NOTE:

1. ALL PROPOSED ENTRANCES TO BE REPLACED IN KIND. AGGREGATE ENTRANCES TO BE REPLACED WITH HOT-MIX ASPHALT.
2. ALL EXISTING TREES TO REMAIN SHALL BE PROTECTED. THIS WORK SHALL BE PAID FOR AS TEMPORARY FENCE.
3. SEE MISCELLANEOUS DETAILS SHEET FOR RAISED CROSSWALK DETAILS.
4. BUS STOP PAD SHALL BE PAID FOR AS PORTLAND CEMENT CONCRETE SIDEWALK, 5".
5. SEE LANDSCAPING PLAN AND DETAIL FOR LOCATION OF TREE PITS AND ADDITIONAL INFORMATION.

LEGEND

REMOVAL ITEM

TREE REMOVAL

EXISTING CENTERLINE PROFILE

PROPOSED CENTERLINE PROFILE

VPI STA 100+00.00
EL 674.70
290.00' V.C.
ex = 1.51'
K = 70

+55.00 EL 676.67

+45.00 EL 678.77

VPI STA 102+16.20
EL 680.77
-1.59%
+2.81%
142.40' V.C.
ex = -0.78'
K = 32

RAISED CROSSWALK (SEE NOTE 3)

-1.36%
+2.80%

FILE NAME =	USER NAME = $USER$	DESIGNED - J.G.	REVISED -
024_650pp07.dgn		DRAWN - E.D.	REVISED -
	PLOT SCALE = 1:20	CHECKED -	REVISED -
	PLOT DATE = 6/15/2010	DATE - 9/23/2009	REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

PLAN AND PROFILE

SCALE: 1"=20' | SHEET NO. 7 OF 11 SHEETS | STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00070-00-PV	DuPAGE	160	24
		CONTRACT NO. 63379		
	ILLINOIS	FED. AID PROJECT		