


- NOTES:**
1. STORM SEWER CONSTRUCTION ALONG WASHINGTON STREET SHALL BE CONSTRUCTED IN SUB-STAGES. TRAFFIC CONTROL AND PROTECTION SHALL BE IN ACCORDANCE WITH IDOT STANDARDS 701501. ONLY DAY - TIME CLOSURES SHALL BE PERMITTED. ALL OPEN TRENCHES SHALL BE COVERED WITH METAL PLATES OR BACKFILLED DURING NON-WORKING HOURS.
 2. TEMPORARY PAVEMENT PATCH SHALL CONSIST OF HMA BINDER COURSE, IL-19.0, N50, 6".



FILE NAME = 032_65@not1_02.dgn	USER NAME = #USER#	DESIGNED - J.G.	REVISED -
PLOT SCALE = 1:20		DRAWN - E.D.	REVISED -
PLOT DATE = 6/15/2010		CHECKED -	REVISED -
		DATE - 9/23/2009	REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

**SUGGESTED MAINTENANCE OF TRAFFIC
STAGE 1**

SCALE: 1"=20' SHEET NO. 4 OF 14 SHEETS STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE. 2652	SECTION 00-00070-00-PV	COUNTY DuPAGE	TOTAL SHEETS 160	SHEET NO. 32
CONTRACT NO. 63379				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				