

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3794	10-00046-00-RS	KENDALL	13	3
CONTRACT NO. 63496				

**SUMMARY OF QUANTITIES**

CODE NO.	PAY ITEM	UNIT	CONST. CODE 1000 TOTAL QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	96
25200110	SODDING, SALT TOLERANT	SQ YD	96
25200200	SUPPLEMENTAL WATERING	UNIT	1
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,150
40600300	AGGREGATE (PRIME COAT)	TON	65
<del>X4060326</del>	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	883
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	242
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,325
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,675
42400800	DETECTABLE WARNINGS	SQ FT	224
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	4,705
<del>E0004548</del>	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	11,045
44000600	SIDEWALK REMOVAL	SQ FT	1,675
<del>E0004562</del>	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	96
44201701	CLASS D PATCHES, TYPE I, 5 INCH	SQ YD	4
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	32
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	43
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	195
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	330
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	110
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	189
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	186
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	53

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

Printed: June 9, 2010 @ 2:27 PM By: Kris Pung - Tab: 03 Quantities - 22x34

COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**VILLAGE OF MONTGOMERY**

NO.	DATE	REVISIONS

**LAKWOOD CREEK DRIVE  
LAPP IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

DATE: JUNE 2010  
PROJECT NO: M00930  
FILE: M00930-CVR  
SHEET **3** OF **13**

Path: \\S:\P\03\M00930\DWG\FINAL ENR\M00930-CVR