

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 1000-2A	TRAFFIC SIGNALS Y031-1F
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	56	56	-
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,854	3,854	-
40600300	AGGREGATE (PRIME COAT)	TON	64	64	-
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3	-
X406 0826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	603	603	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	159	159	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	31	31	-
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,363	1,363	-
42001300	PROTECTIVE COAT	SQ YD	399	399	-
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	103	103	-
42400800	DETECTABLE WARNINGS	SQ FT	80	80	-
44000100	PAVEMENT REMOVAL	SQ YD	23	23	-
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	13,040	13,040	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	100	100	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,565	1,565	-
44000600	SIDEWALK REMOVAL	SQ FT	1,675	1,675	-
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	587	587	-
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	131	131	-
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	131	131	-
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	652	652	-
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	392	392	-
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	12	12	-
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	245	245	-
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	12	12	-
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	281	281	-
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	376	376	-
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	72	72	-
55100500	STORM SEWER REMOVAL 12"	FOOT	168	168	-
55100700	STORM SEWER REMOVAL 15"	FOOT	7	7	-
55101400	STORM SEWER REMOVAL 30"	FOOT	289	289	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 384-0022-EXPRES 4/27/2010
 PROJECT NO. - 090772-SM-Y-2.dgn
 DATE - 4-27-10
 DRAWN - UKB
 CHECKED - RWL
 DATE - 4-27-10



DESIGNED -	DJS	REVISED -	6-8-10 IDOT REVIEW
DRAWN -	UKB	REVISED -	
CHECKED -	RWL	REVISED -	
DATE -	4-27-10	FILE -	090772-SM-Y-2.dgn

VILLAGE OF GRAYSLAKE, ILLINOIS
ATKINSON ROAD RESURFACING
AND RECONSTRUCTION IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0198	09-00058-00-RS	LAKE	46	5
CONTRACT NO. 63498				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT: M-9003 (485)				