

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY I000-2A	TRAFFIC SIGNALS Y031-1F
55101600	STORM SEWER REMOVAL 36"	FOOT	613	613	-
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	16	16	-
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2	2	-
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	-
60222000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1	-
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	-
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	9	9	-
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	1	1	-
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5	-
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3	-
60260100	INLETS TO BE ADJUSTED	EACH	4	4	-
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2	-
60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2	-
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10	-
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	-
60500040	REMOVING MANHOLES	EACH	3	3	-
60500050	REMOVING CATCH BASINS	EACH	2	2	-
60500060	REMOVING INLETS	EACH	5	5	-
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,605	1,605	-
67100100	MOBILIZATION	L SUM	1	1	-
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1	-
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	-
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	-
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	-
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,097	3,097	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,033	1,033	-
72000100	SIGN PANEL - TYPE 1	SQ FT	27	-	27
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296	296	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 184-00121 - EXPIRES 4/30/2011
 133 S. 75th ST. LAKE FOREST, IL 60045-1201
 (630) 484-1100 FAX (630) 484-1101



DESIGNED - DJS	REVISED - 6-8-10 IDOT REVIEW
DRAWN - UKB	REVISED - 7-12-10 IDOT REVIEW
CHECKED - RWL	REVISED -
DATE - 4-27-10	FILE - 090772-SMY-QTY-3.dgn

**VILLAGE OF GRAYSLAKE, ILLINOIS
ATKINSON ROAD RESURFACING
AND RECONSTRUCTION IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0198	09-00058-00-RS	LAKE	46	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT: M-9003 (485)			CONTRACT NO. 63498	