SUMMARY OF QUANTITIES

	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY I000-2A	TRAFFIC SIGNALS Y031-1F
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,880	9,880	-
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,617	1,617	-
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	940	940	-
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155	155	-
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	425	-	425
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	41	-	41
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	20	-	20
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	201	-	201
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	184	-	184
*	81400100	HANDHOLE	EACH	6	-	6
*	81400200	HEAVY-DUTY HANDHOLE	EACH	1	-	1
*	81400300	DOUBLE HANDHOLE	EACH	1	-	1
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	471	-	471
*	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	-	1
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	368	-	368
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	635	-	635
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,155	-	1,155
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	338	-	338
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	977	-	977
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	87	-	87
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1	-	1
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	-	1
*	87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1	-	1
*	87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	2	-	2
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	-	8
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	-	4
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	37	-	37
*	88000160	SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3	-	3
*	88000170	SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5	-	5
*	88000290	SIGNAL HEAD, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1	-	1

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001172 EXPIRES 4/30/2011
Last revised: 4/27/2010 4:49:25 PM
...\plotdrv\xb172pxl4.cpt
...\Plotted\090772-SMY-QTY-4.dgn
...\Cover Sheet\GRAY\090772-A-Atkinson PhvCADD SURVEY\DRAWINGS\DGNS\sheets\phase 2\090772-SMY-QTY-4.dgn

BAXTER & WOODMAN Consulting Engineers	DESIGNED - DJS	REVISED - 6-8-10 IDOT REVIEW	VILLAGE OF GRAYSLAKE, ILLINOIS ATKINSON ROAD RESURFACING AND RECONSTRUCTION IMPROVEMENTS
	DRAWN - UKB	REVISED -	
	CHECKED - RWL	REVISED -	
	DATE - 4-27-10	FILE - 090772-SMY-QTY-4.dgn	

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0198	09-00058-00-RS	LAKE	46	7
		CONTRACT NO. 63498		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT: M-9003 (485)