

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

ROADWAY Y007 80% FED 20% STATE TOTAL QUANTITY
--------------------------------------------------------------

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	92
20400800	FURNISHED EXCAVATION	CU YD	11
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	640
* 25100630	EROSION CONTROL BLANKET	SQ YD	729
* 25100900	TURF REINFORCEMENT MAT	SQ YD	52
28000305	TEMPORARY DITCH CHECKS	FOOT	80
28000400	PERIMETER EROSION BARRIER	FOOT	385
28000500	INLET AND PIPE PROTECTION	EACH	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	34
28200200	FILTER FABRIC	SQ YD	34
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	94
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	150
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1
51500100	NAME PLATES	EACH	1
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	110
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	36
63500105	DELINEATORS	EACH	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	688
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

\* SPECIALTY ITEM

WHITESIDE COUNTY SECTION 15T-1

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwork\pwork\cushmanbw\149475\12099901-sht-schedule.dgn		DRAWN -	REVISED -			22	15T-1	WHITESIDE	17	2	
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.					
PLOT DATE = Thu Jun 24 08:48:10 2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 64F35					