

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNITS	URBAN TOTAL QTY.	90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE 5% CO	90% FED 10% STATE	100% CO	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
				ROADWAY HMA 1000-2A	ROADWAY CONCRETE J000-2A	SIGNAL ITEMS Y030-1E	LIGHTING Y030-1E	DIFF. OF ULT. VS. INT. 1000-2A	BRIDGE BRISBIN X231-2A	BRIDGE RAMP B X081-2A	BRIDGE RAMP C X081-2A
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1						
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	21		21						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	61		58	3					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	384		384						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	49,474		49,474						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	83		83						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18,230		18,230						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	19,466		19,466						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5,926		5,926						
72000100	SIGN PANEL - TYPE 1	SQ FT	626		570	56					
72000200	SIGN PANEL - TYPE 2	SQ FT	310		310						
72000300	SIGN PANEL - TYPE 3	SQ FT	1,604		1,604						
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	18		18						
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	60		60						
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	8,737		8,737						
72700200	TUBULAR STEEL SIGN SUPPORT - BREAKAWAY	POUND	400		400						
73000100	WOOD SIGN SUPPORT	FOOT	1,561		1,561						
73400100	CONCRETE FOUNDATIONS	CU YD	21		21						
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	2		2						
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2		2						
78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS	SQ FT	780		780						
78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	72,228		72,228						
78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	5,903		5,903						
78008340	POLYUREA PAVEMENT MARKING TYPE II - LINE 8"	FOOT	16,714		16,714						
78008350	POLYUREA PAVEMENT MARKING TYPE II - LINE 12"	FOOT	6,577		6,577						
78008370	POLYUREA PAVEMENT MARKING TYPE II - LINE 24"	FOOT	350		350						
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,294		1,294						
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20		20						
78200300	PRISMATIC CURB REFLECTOR	EACH	205		205						
78200410	GUARDRAIL MARKERS, TYPE A	EACH	34		34						
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7		7						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4539		4539						
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2				2				
80500200	SERVICE INSTALLATION, TYPE B	EACH	1			1					
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	2,395			2,395					
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	30			30					
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	154			154					
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	52			52					
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	55				55				
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	840				840				
81020700	CONDUIT PUSHED, 3" DIA., INTERMEDIATE METAL	FOOT	145				145				
81020900	CONDUIT PUSHED, 4" DIA., INTERMEDIATE METAL	FOOT	85				85				
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	45			45					
81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	437			437					
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	28			28					

\* SPECIALTY ITEM

FILE NAME = t:\18126CADD Sheets\0366408-sht-500.dgn	USER NAME = .USER.	DESIGNED - CGC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = #SCALE#	CHECKED - JPW	REVISED -	(32,47-4) HBK-4 & G(N)			GRUNDY	351	7		
PLOT DATE = 5/21/2010	DATE - 5/21/2010	REVISED -	CONTRACT NO. 66408							
			ILLINOIS FED. AID PROJECT							
SCALE: NONE						SHEET NO. 7 OF 351 SHEETS		STA. TO STA.		

• FAI 80 & FAS 297 / FAU 392