

ITEM 20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)			
LOCATION	STATION	OFFSET	UNIT
US 6	206+07.53	-87.62	18
US 6	207+15.76	-67.1	24
BRISBIN RD	100+34.39	47.78	24
BRISBIN RD	100+78.88	-29.85	24
BRISBIN RD	101+19.29	-75.84	24
BRISBIN RD	101+11.04	-100.45	36
BRISBIN RD	102+27.10	72.15	20
BRISBIN RD	103+33.99	40.85	52
BRISBIN RD	104+75.65	24.91	36
BRISBIN RD	127+77.67	29.21	18
BRISBIN RD	127+10.53	37.61	48
BRISBIN RD	102+34.62	23.34	20
BRISBIN RD	102+42.68	23.83	22
BRISBIN RD	112+29.05	24.53	28
BRISBIN RD	112+86.73	38.11	30
BRISBIN RD	113+48.48	33.35	22
BRISBIN RD	114+03.40	64.2	32
BRISBIN RD	116+40.18	40.69	22
BRISBIN RD	116+96.75	-23.32	24
BRISBIN RD	103+78.73	21.14	18
BRISBIN RD	103+78.69	23.46	18
BRISBIN RD	103+78.44	26.18	24
I-80	1395+55.95	-90.73	18
I-80	1393+48.37	-90.57	30
I-80	1392+56.65	-98.15	30
I-80	1396+27.40	-81.72	36
I-80	1399+09.85	-97.1	26
I-80	1392+55.27	-99.01	15
I-80	1392+57.55	-96.74	15
I-80	1399+71.41	-99.83	16
I-80	1401+90.13	-99.8	19
I-80	1398+09.11	110.6	30
I-80	1400+28.27	108.57	24
I-80	1400+56.32	109.47	24
NORTH RD	8+15.90	-23.22	30
RAMP A	113+92.40	212.64	36
RAMP A	114+57.15	219.27	18
RAMP A	114+63.61	219.2	19
RAMP A	112+54.23	194.4	38
RAMP A	113+11.95	198.7	18
RAMP A	113+64.95	214.96	18
RAMP A	111+87.59	172.26	30
RAMP A	110+69.32	136.22	17
RAMP A	111+08.99	145.79	16
RAMP A	109+67.41	63.14	17
RAMP A	109+86.73	92.28	16
RAMP A	109+36.28	2.12	32
RAMP A	108+78.03	-3.42	30
RAMP A	109+07.64	14.32	16
RAMP A	108+15.37	5.75	20
RAMP A	108+20.21	7.62	30
RAMP A	108+27.28	6.91	20
RAMP A	107+40.42	13.94	24
RAMP A	105+96.72	20.1	15
RAMP A	105+97.99	20.87	15
RAMP A	105+95.08	18.79	15
RAMP B	214+85.87	-75.88	34
RAMP B	214+99.23	-71.3	15
RAMP B	215+06.20	-42.42	15
RAMP B	215+07.73	-41.54	15
RAMP B	215+05.60	-40.22	15
RAMP B	215+27.96	0.7	15
RAMP B	214+96.09	-1.16	16
RAMP B	214+85.47	-47.39	30
RAMP B	214+73.50	-36.39	32
RAMP B	214+66.73	-30.76	32
RAMP B	214+63.63	-35.37	28
RAMP B	214+53.82	17.99	48
RAMP B	214+88.48	57.88	20
RAMP B	214+42.66	0.92	15
RAMP B	223+86.12	20.72	48
RAMP B	223+88.10	20.71	48
RAMP B	223+88.46	21.78	48
RAMP B	222+50.97	29.55	20
RAMP B	215+94.52	45.27	30

ITEM 20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)			
LOCATION	STATION	OFFSET	UNIT
RAMP B	215+89.09	21.3	25
RAMP B	215+89.70	13.5	25
RAMP B	215+90.40	13.68	25
RAMP B	215+98.54	-19.11	18
RAMP B	216+78.65	-2.07	15
RAMP B	216+84.60	10.27	24
RAMP B	216+46.01	-4.04	24
RAMP B	216+26.46	-43.91	24
RAMP B	217+78.33	-5.55	24
RAMP B	217+80.49	-5.14	18
RAMP B	217+65.91	-8.61	18
RAMP B	217+54.48	18.18	20
RAMP B	217+28.30	-17.87	26
RAMP B	217+95.32	35.36	20
RAMP B	217+97.18	34.21	18
RAMP B	218+09.08	36.73	34
RAMP B	218+26.41	4.44	28
RAMP B	218+08.75	0.82	15
RAMP B	218+47.54	5.9	16
RAMP B	218+65.33	8.73	17
RAMP B	219+50.40	19.25	30
RAMP B	219+79.54	21.02	16
RAMP B	219+81.79	21.23	16
RAMP B	220+57.43	27.97	25
RAMP B	220+69.60	32.86	26
RAMP B	220+61.42	33.95	28
RAMP B	220+92.84	23.59	48
RAMP B	220+99.26	23.11	40
RAMP B	218+58.19	43.07	16
RAMP B	216+46.71	45.28	20
RAMP B	216+95.32	79.33	46
RAMP B	219+75.72	78.35	15
RAMP B	220+62.51	77.63	27
RAMP B	221+67.07	77.39	32
RAMP B	231+18.96	46.17	25
RAMP B	226+76.09	44.64	18
RAMP B	214+89.81	60.55	20
RAMP B	218+09.68	50.27	15
RAMP B	220+41.75	39.47	26
RAMP B	222+80.67	37.04	20
RAMP B	215+31.57	63	19
RAMP B	216+03.19	63.9	15
RAMP B	223+50.62	40.6	30
RAMP C	308+15.90	47.84	16
RAMP C	308+67.77	52.21	22
RAMP C	309+26.46	23.72	22
RAMP C	309+20.11	53.82	18
RAMP C	309+87.11	45.11	20
RAMP C	309+87.63	46.15	22
RAMP C	305+94.18	65.72	15
RAMP D	400+20.83	90.75	20
RAMP D	413+18.62	-57.54	20
TOTAL			3063

ITEM 20101000 TEMPORARY FENCE	
LOCATION	LENGTH (FT)
BRISBIN ROAD	7883
TOTAL	7883

ITEM 20001050 AGGREGATE SUBGRADE 12"	
LOCATION	AREA (SQ YD)
STATION TO STATION	
BRISBIN ROAD	
87+53.10 TO 96+08.10	4780
96+08.10 TO 98+47.65	2390
99+63.22 TO 113+37.69	13755
116+62.15 TO 130+30.33	11474
US ROUTE 6	
189+74.73 TO 200+36.59	6416
200+36.59 TO 207+14.40	8004
207+14.40 TO 215+09.62	4901
I-80	
1359+54.64 TO 1372+08.41	767
1361+03.89 TO 1377+44.85	1216
1392+45.64 TO 1397+53.31	855
1394+90.18 TO 1398+09.88	949
1396+95.50 TO 1402+22.00	873
1417+34.57 TO 1433+69.74	1176
1425+20.44 TO 1436+61.07	805
RAMP A	
106+60.00 TO 117+12.00	3491
RAMP B	
200+46.56 TO 215+18.44	4953
216+52.60 TO 219+61.36	899
RAMP C	
306+60.00 TO 308+07.93	729
309+34.29 TO 317+56.10	3757
RAMP D	
416+04.82 TO 428+77.79	5007
NORTH ROAD	
00+14.92 TO 09+50.67	3038
SERVICE DRIVE	
00+17.56 TO 00+59.13	169
TOTAL	80402

EARTHWORK SCHEDULE						
1 LOCATION STATION VOLUME (CU YD)	2 20200100 EARTH EXCAVATION	3 20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	4 EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	5 20400800 FURNISHED EXCAVATION (EMBANKMENT)	6 EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	7 21101505 TOPSOIL EXCAVATION AND PLACEMENT
BRISBIN						
99+00.00 TO 130+00.00	14264		11411	128861	-117450	4145
BRISBIN STAGE 1						
88+00.00 TO 98+00.00	300		240	119	121	0
BRISBIN STAGE 2						
88+00.00 TO 98+00.00	1921		1537	1712	-175	0
BRISBIN STAGE 3						
88+00.00 TO 98+00.00	4434		3547	2059	1488	0
BRISBIN STAGE 5						
88+00.00 TO 98+00.00	1679		1343	0	1343	0
US ROUTE 6						
205+62.81	48		38	0	38	0
205+70.74	62		50	0	50	0
US ROUTE 6 STAGE 1						
188+00.00 TO 217+00.00	32		25	304	-279	0
US ROUTE 6 STAGE 2						
188+00.00 TO 217+00.00	1565		1252	4579	-3327	0
US ROUTE 6 STAGE 3						
188+00.00 TO 217+00.00	1318		1054	5748	-4694	704
US ROUTE 6 STAGE 4						
188+00.00 TO 217+00.00	167		133	1	132	0
US ROUTE 6 STAGE 5						
188+00.00 TO 217+00.00	1504		1203	1084	119	747
I-80						
1360+00 TO 1377+00	1119		895	101	794	405
1393+00 TO 1402+00	1869		1495	527	968	143
1418+00 TO 1433+00	879		703	16	687	193
RAMP A						
100+00.00 TO 116+00.00	1633	849	1307	47022	-45715	2611
RAMP B						
201+00.00 TO 232+00.00	20254	3953	16204	45560	-29356	4823
RAMP C						
300+00.00 TO 317+00.00	1558	2537	1247	27176	-25929	1341
RAMP D						
402+00.00 TO 428+00.00	8462	1118	6770	16288	-9518	2523
NORTH RD						
1+00.00 TO 9+00.00	6460		5168	304	4864	547
SERVICE DRIVE						
1+00.00 TO 16+00.00	1660		1328	2736	-1544	1055
TOTAL	71188	8457	56950	284197	-227383	19237

ITEM 20001058 AGGREGATE SUBGRADE 18"	
LOCATION	AREA (SQ YD)
STATION TO STATION	
RAMP C	
300+00.00 TO 306+60.00	1882
RAMP D	
428+77.79 TO 416+04.82	2892
TOTAL	4774

ITEM 20001060 AGGREGATE SUBGRADE 24"	
LOCATION	AREA (SQ YD)
STATION TO STATION	
RAMP A	
100+00.00 TO 106+60.00	1921
RAMP B	
219+61.36 TO 232+50.12	2993
TOTAL	4914

FILE NAME =  
t:\1812\CAOD Sheets\20366408-sht-sched.dgn

USER NAME = .USER.  
PLOT SCALE = #SCALE#  
PLOT DATE = 6/23/2010

DESIGNED - ECS  
DRAWN - ECS  
CHECKED - CGC  
DATE - 6/23/2010

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 19 OF 351 SHEETS STA. TO STA.

\* FAI 80 & FAS 297 / FAU 392

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	(32,47-4) HBK-4 & (G)N	GRUNDY	351	19
CONTRACT NO. 66408				
ILLINOIS FED. AID PROJECT				