

ITEM 70300100 SHORT-TERM PAVEMENT MARKING	
LOCATION	LENGTH (FT)
STAGE 5	
BRISBIN ROAD	192
US ROUTE 6	192
TOTAL	384

ITEM 70300220 TEMPORARY PAVEMENT MARKING	
LOCATION	LINE - 4" (FT)
STAGE 2	
US ROUTE 6	
181+75.00 TO 203+10.00	12813.75
BRISBIN RD	
83+53.00 TO 98+74.00	4652.20
STAGE 3	
US ROUTE 6	
181+75.00 TO 203+10.00	12949.50
BRISBIN RD	
83+53.00 TO 99+12.00	4361.40
STAGE 4	
US ROUTE 6	
181+75.00 TO 203+10.00	115.00
BRISBIN RD	
96+30 TO 98+94	977.40
STAGE 5	
US ROUTE 6	
181+75.00 TO 203+10.00	8714.50
198+96.00 TO 200+36.00	23.25
208+80.00 TO 210+78.00	50.00
BRISBIN RD	
83+53.00 TO 99+58.00	4697.20
92+18.00 TO 94+28.00	52.50
93+38.00 TO 96+08.00	67.50
TOTAL	49474

ITEM 70300280 TEMPORARY PAVEMENT MARKING	
LOCATION	LINE - 24" (FT)
STAGE 2 BRISBIN RD	
98+74.00	12.5
STAGE 3 BRISBIN RD	
99+12	14
STAGE 4 BRISBIN RD	
98+93	12
STAGE 5 BRISBIN RD	
98+58	44.5
TOTAL	83

ITEM 70301000 WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	AREA (SQ FT)
STAGE 2	
US ROUTE 6	1325
BRISBIN RD	202
STAGE 3	
BRISBIN RD	339
STAGE 4	
US ROUTE 6	4333
BRISBIN RD	1606
STAGE 5	
US ROUTE 6	2911
BRISBIN RD	1665
STAGE 5 I-80	5850
TOTAL	18230

ITEM 70400100 TEMPORARY CONCRETE BARRIER	
LOCATION	LENGTH (FT)
STAGE 1 I-80	
1359+55 TO 1437+07	15102
STAGE 2	
BRISBIN ROAD	
203+96 TO 208+14	1675
US ROUTE 6	
188+90 TO 216+11	2689
TOTAL	19466

ITEM 70400200 RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	LENGTH (FT)
STAGE 4	
I-80	50
STAGE 5	
I-80	1602
STAGE 3	
BRISBIN ROAD	1293
US ROUTE 6	2638
STAGE 4	
BRISBIN	343
TOTAL	5926

ITEM 78100100 RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
BRISBIN ROAD	417
RAMP A	86
RAMP C	88
I-80	527
US ROUTE 6	176
TOTAL	1294

ITEM 78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	
LOCATION	EACH
BRISBIN ROAD	16
RAMP C	4
TOTAL	20

POLYUREA PAVEMENT MARKING TYPE II						
LOCATION	78008300 LETTERS & SYMBOLS	78008310 LINE - 4" (FT)	78008330 LINE - 6" (FT)	78008340 LINE - 8" (FT)	78008350 LINE - 12" (FT)	78008370 LINE - 24" (FT)
BRISBIN ROAD	327.6	12609	981	3521	932	350
RAMP A		2609		1515	80	
RAMP B		5112		2102	63	
RAMP C	93.6	2260	51	2211	781	
RAMP D		4217		2232		
I-80	172	28263	4621	1674	2416	
US ROUTE 6	187.2	13576	250	3458	2305	
NORTH ROAD		3582				
TOTAL	780	72228	5903	16714	6577	350

ITEM X7030140 PAVEMENT MARKING TAPE, TYPE III 6", SPECIAL		
LOCATION	LINE - 6" YELLOW (FT)	LINE - 6" WHITE (FT)
STAGE 5		
I-80	3900	7800
SUB-TOTAL		
	3900	7800
TOTAL	11700	

FILE NAME =	USER NAME = .USER.	DESIGNED - ECS	REVISED -
t:\1812\cadd sheets\0366408-sht-schedule.dgn		DRAWN - ECS	REVISED -
PLOT SCALE = #SCALE#		CHECKED - CGC	REVISED -
PLOT DATE = 5/21/2010		DATE - 5/21/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 29 OF 351 SHEETS STA. TO STA.

• FAI 80 & FAS 297 / FAU 392

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	(32,47-4) HBK-4 & G(N)	GRUNDY	351	29
			CONTRACT NO. 66408	
ILLINOIS FED. AID PROJECT				