

ITEM 78200300 PRISMATIC CURB REFLECTOR	
LOCATION	EACH
BRISBIN ROAD	156
US ROUTE 6	49
TOTAL	205

ITEM 78300105 PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
I-80	3,046
US ROUTE 6	1,493
TOTAL	4,539

ITEM X0919000 TEMPORARY PAVEMENT REMOVAL	
LOCATION STATION TO STATION	AREA SQ YD
STAGE 1	
US ROUTE 6	
182+80.00 TO 198+12.00	1588.31
209+64.00 TO 222+20.00	1245.52
BRISBIN ROAD	
83+53.00 TO 98+41.00	1838.97
STAGE 3	
US ROUTE 6	
182+20.00 TO 200+37.00	2724.85
207+14.00 TO 210+35.00	318.56
210+65.00 TO 221+84.00	1305.00
BRISBIN ROAD	
83+53.00 TO 96+08.00	1721.98
98+68.00 TO 98+92.00	45.93
TOTAL	10789

ITEM 78200410 GUARDRAIL MARKERS, TYPE A			
LOCATION STATION TO STATION	LT / RT	UNIT	
BRISBIN ROAD			
111+36.09 TO 113+91.82	RT	3	
116+08.02 TO 118+63.93	LT	3	
I-80			
1392+88.81 TO 1397+51.31	RT	6	
1396+97.50 TO 1401+60.00	LT	6	
1433+50.71 TO 1437+06.35	RT	4	
RAMP B			
212+25.36 TO 215+18.50	LT	4	
212+41.80 TO 215+09.96	RT	3	
RAMP C			
303+92.73 TO 307+85.88	RT	5	
TOTAL		34	

ITEM X0321156 HIGH VISIBILITY TEMPORARY FENCING		
LOCATION STATION TO STATION	OFFSET	LENGTH (FT)
NORTH ROAD		
07+75.89 TO 09+45.27	65	215
08+76.77 TO 09+56.08	-32.49	95
I-80		
1406+75.44 TO 1408+72.52	-188.21	214
1409+39.56 TO 1416+01.96	-155.75	685
TOTAL		1209

ITEM X0322671 STABILIZED CONSTRUCTION ENTRANCE	
LOCATION STATION TO STATION	AREA (SQ YD)
1	182
2	182
3	182
4	182
TOTAL	728

ITEM Z0007550 BUILDING REMOVAL	
LOCATION STATION	(EACH)
BRISBIN RD	
102+52.21	1
NORTH RD	
02+38.89	1
02+68.06	1
03+00.26	1
03+14.52	1
03+08.84	1
02+94.13	1
02+42.63	1
02+23.90	1
02+04.12	1
TOTAL	10

ITEM 78201000 TERMINAL MARKER - DIRECT APPLIED		
LOCATION STATION	OFFSET	UNIT
BRISBIN ROAD		
111+36.09	42.66	1
118+63.93	-47.45	1
I-80		
1392+88.81	65.80	1
1401+60.00	-65.80	1
RAMP B		
212+25.36	-24.67	1
212+41.80	11.00	1
RAMP C		
303+92.73	11.63	1
TOTAL		7

ITEM X0325887 POUROUS GRANULAR CAPPING MATERIAL	
LOCATION STATION TO STATION	WEIGHT (TON)
RAMP A	
110+00 TO 116+00	5952
BRISBIN RD	
108+00 TO 112+00	1412
TOTAL	7364

ITEM X0326372 REMOVE RIGHT-OF-WAY MARKERS			
LOCATION STATION	LT / RT	OFFSET	UNIT
US ROUTE 6			
204+64.58	RT	80	1
206+98.86	RT	70	1
RAMP B			
225+02.87	RT	34	1
TOTAL			3