

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE Y009	
				ROADWAY	RURAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	49	49	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	37	37	
20200100	EARTH EXCAVATION	CU YD	707	707	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1933	1933	
20400800	FURNISHED EXCAVATION	CU YD	2968	2968	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	863	863	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3212	3212	
25000300	SEEDING, CLASS 3	ACRE	0.75	0.75	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	60	60	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	60	60	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	60	60	
25100115	MULCH, METHOD 2	ACRE	0.75	0.75	
25100630	EROSION CONTROL BLANKET	SQ YD	2993	2993	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	140	140	
28000305	TEMPORARY DITCH CHECKS	FOOT	49	49	
28000400	PERIMETER EROSION BARRIER	FOOT	473	473	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100105	STONE RIPRAP, CLASS A3	SQ YD	323	323	
28100107	STONE RIPRAP, CLASS A4	SQ YD	39	39	
28100125	STONE RIPRAP, CLASS B3	SQ YD	180	180	
28200200	FILTER FABRIC	SQ YD	82	82	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	153	153	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE Y009	
				ROADWAY	RURAL
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2	
50105220	PIPE CULVERT REMOVAL	FOOT	53	53	
50800105	REINFORCEMENT BARS	POUND	60	60	
52100510	ANCHOR BOLTS, 3/4"	EACH	16	16	
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	20	20	
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	29	29	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
54248510	CONCRETE COLLAR	CU YD	1.5	1.5	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4	
60100080	FRENCH DRAINS	CU YD	33.5	33.5	
60100905	PIPE DRAINS 4"	FOOT	177	177	
60109620	BACKSLOPE DRAINS, TYPE 2, 4"	FOOT	775	775	
63200310	GUARDRAIL REMOVAL	FOOT	200	200	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	LSUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4800	4800	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1584	1584	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	300	300	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1800	1800	

*SPECIALTY ITEM

FILE NAME = D468974-sht-500.dgn	USER NAME = crespole	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL RTE 41 SLOPE REPAIR SUMMARY OF QUANTITIES	F.A.P. RTE. 574	SECTION 12I-1	COUNTY Fulton	TOTAL SHEETS 31	SHEET NO. 4	CONTRACT NO. 68974
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		[ILLINOIS] FED. AID PROJECT					
PLOT DATE = 6/21/2010		DATE -	REVISED -								