

MULCH, METHOD 2	
LOCATION	ACRE
Rt. Sta 211+25 to Sta 215+00	0.58
Lt. Sta 211+25 to Sta 215+00	0.17
TOTAL = 0.75	

EROSION CONTROL BLANKET	
LOCATION	SQ YD
Rt. Sta 211+25 to Sta 215+00	2,385
Lt. Sta 211+25 to Sta 215+00	608
TOTAL = 2,993	

TEMPORARY EROSION CONTROL SEEDING	
LOCATION	POUND
Rt. Sta 211+25 to Sta 215+00	107.00
Lt. Sta 211+25 to Sta 215+00	33.00
TOTAL = 140.0	

Note: 2 Applications

TEMPORARY DITCH CHECKS	
LOCATION	FOOT
Lt. Sta. 212+77.41	10
Lt. Sta 213+06.80	15
Lt. Sta. 213+51.31	12
Lt. Sta 213+79.08	12
TOTAL = 49	

PERIMETER EROSION BARRIER	
LOCATION	FOOT
Rt. Sta. 211+38.68 to Sta. 215+05.88	473
TOTAL = 473	

INLET AND PIPE PROTECTION	
LOCATION	EACH
Lt. Sta. 213+20.68	1
Rt. Sta 213+34.85	1
TOTAL = 2	

STONE RIPRAP, CLASS A3	
LOCATION	SQ YD
Rt. Sta. 212+25	30
Rt. Sta. 212+27.4 to Sta. 213+34.2	165
Rt. Sta. 212+44.2 to Sta. 214+05.3	128
TOTAL = 323	

STONE RIPRAP, CLASS A4	
LOCATION	SQ YD
Lt. Sta. 213+20.68	11
Rt. Sta 213+34.85	28
TOTAL = 39	

STONE RIPRAP, CLASS B3	
LOCATION	SQ YD
Lt. Sta. 212+50 to Sta. 213+15.03	84
Lt. Sta. 213+24.38 to Sta. 214+06.66	96
TOTAL = 180	

FILTER FABRIC	
LOCATION	SQ YD
Lt. Sta. 213+20.68	11
Rt. Sta 212+25.00	43
Rt. Sta 213+34.85	28
TOTAL = 82	

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	
LOCATION	SQ YD
Rt. Sta. 212+00.00 to Sta. 214+00.00	863
TOTAL = 863	

AGGREGATE SHOULDERS, TYPE B	
LOCATION	TON
Lt. Sta. 212+00 to Sta. 214+50	64
Rt. Sta 211+50 to Sta. 215+00	89
TOTAL = 153	

CONCRETE HEADWALL REMOVAL	
LOCATION	EACH
Lt. Sta. 212+82.1	1
Lt. Sta. 213+26.08	1
TOTAL = 2	

PIPE CULVERT REMOVAL	
LOCATION	FOOT
Lt. Sta. 212+81.72 to Sta. 213+23.75 , 12" Dia. (CMP)	43
Lt. Sta. 213+25.96 (CMP)	10
TOTAL = 53	

PIPE CULVERTS, CLASS A, TYPE 2, 30"	
LOCATION	FOOT
Lt. Sta. 213+25.96	22
TOTAL = 22	

PIPE CULVERTS, CLASS A, TYPE 2, 36"	
LOCATION	FOOT
Rt. Sta. 213+25.96	29
TOTAL = 29	

FILE NAME = D468974-sht-schedule.dgn

USER NAME = crespole

DESIGNED -

DRAWN -

CHECKED -

DATE -

REVISED -

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE 41 SLOPE REPAIR
SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	12I-1	Fulton	31	9

CONTRACT NO. 68974
ILLINOIS FED. AID PROJECT