

WORK ZONE PAVEMENT MARKING REMOVAL		
LOCATION	SQ FT	
EXISTING	EDGE (WHITE)	CENTERLINE (SKIP DASH)
Rt. Sta. 209+00 - 217+00	264	
Lt. Sta. 209+00 - 217+00	264	
Sta. 209+00 - 217+00		132
STAGE 1	EDGE (WHITE)	CENTERLINE (DOUBLE YELLOW)
Rt. Sta. 209+00 - 217+00	264	
Lt. Sta. 209+00 - 217+00	264	
Sta. 209+00 - 217+00		528
STAGE 2		
Rt. Sta. 211+00 - 215+00	132	
Lt. Sta. 211+00 - 215+00	132	
Sta. 211+00 - 215+00		264
TOTAL = 2,244		

FENCE REMOVAL	
LOCATION	FOOT
Rt. Sta. 211+00 to Sta. 212+48	147
Rt. Sta. 212+48	10
Rt. Sta. 212+48 to Sta. 213.95.74	145
Rt. Sta. 213+95.74	13
Rt. Sta. 213+95.74 to Sta. 216+00	205
TOTAL = 520	

ROCK FILL	
LOCATION	TON
Rt. Sta. 212+25 to 214+00	828
TOTAL = 828	

IMPACT ATTENUATOR, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
Lt. Sta. 211+75	1
Lt. Sta. 214+79	1
TOTAL = 2	

TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
Rt. Sta. 211+25 to 215+25	400
TOTAL = 400	

IMPACT ATTENUATOR, TEMPORARY (FULLY-REDIRECTIVE NARROW), TEST LEVEL 3	
LOCATION	EACH
Rt. Sta. 211+25	1
Rt. Sta. 215+30	1
TOTAL = 2	

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
Lt. Sta. 211+75 to 214+75	300
TOTAL = 300	

CONSTRUCTION LAYOUT	
LOCATION	L. SUM
Jobsite	1
TOTAL = 1	

FILE NAME = 0468974-sh-t-schedule.dgn

USER NAME = crespole

DESIGNED -

DRAWN -

CHECKED -

DATE -

REVISED -

REVISED -

REVISED -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL RTE 41 SLOPE REPAIR
SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	12I-1	Fulton	31	11
CONTRACT NO. 68974				

ILLINOIS FED. AID PROJECT