

HOT MIX ASPHALT SCHEDULE

LOCATION	TEMPORARY RAMP	HMA BINDER CRSE, IL-19.0, N70	POLY HMA SURF CRSE, MIX "D", N70	BIT MATLS (PRIME COAT)	AGG PRIME COAT	HMA SURF REM - BUTT JOINT	HMA SURF REM 2"	INCIDENTAL HMA SURFACING
	SQ YD	TON	TON	TON	TON	SQ YD	SQ YD	TON
STA. 65+00 TO STA. 65+05	45							
STA. 65+00 TO STA. 65+40						318		
STA. 65+79.19 RT - TEAL DR.	19					183		
STA. 65+00 TO STA. 67+51.96		653	226	0.7	3.5			
STA. 69+44.04 TO STA. 73+00		1144	242	0.8	4.0			
STA. 70+57.14 LT - COTTONWOOD ST	16					31		
STA. 71+60 TO STA. 73+00						690		
STA. 73+00 TO STA. 121+00			2634	7.7	38.5		23467	
STA. 120+93.33 TO STA. 121+00	33							
COTTONWOOD DRIVE IMPACT ATTENUATORS		16						
FROM SIDE ROAD SCHEDULE	359		39	0.7	3.3	2213		211
TOTAL	472	1797	3141	9.9	49.3	3435	23467	211

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH (FT)	PAVEMENT MK. REMOVAL		SHORT TERM PVMT. MARKING		WORK ZONE PAVEMENT MK. REMOVAL		TEMPORARY PAVEMENT MARKING LINE - 5"		TEMPORARY PAVEMENT MARKING LINE - 24"	
		WHITE (SQ. FT)	YELLOW SKIP DASH & NO PASSING (SQ. FT)	WHITE (FT)	YELLOW (FT)	WHITE (SQ FT)	YELLOW SKIP DASH & NO PASSING (SQ FT)	WHITE (FT)	YELLOW (FT)	WHITE (FT)	YELLOW (FT)
STA. 65+00 TO STA. 70+10 LT.	510	214									
STA. 65+00 TO STA. 67+00 LT. (SKIP DASH)	200	21									
STA. 66+20 TO STA. 67+29 LT.	109	46									
STA. 66+30 TO STA. 70+12 LT. (DBL. SOLID)	382		319								
STA. 68+40 TO STA. 70+12 RT.	172	72									
STA. 70+93 TO STA. 73+87 LT.	294		123								
STA. 70+93 TO STA. 73+87 LT. (SKIP DASH)	294		34								
STA. 70+93 TO STA. 73+87 LT.	294		123								
STA. 72+20 TO STA. 73+87 RT. (SKIP DASH)	167		34								
STA. 66+52 - LT. TURN ARROW		15.6									
STA. 67+31 - LT. TURN ARROW		15.6									
STA. 69+18 - LT. TURN ARROW		15.6									
STA. 69+95 - LT. TURN ARROW		15.6									
STA. 65+00 TO STA. 73+00	800			225		94					
STA. 73+00 TO STA. 121+00	4800			1355		565					
STAGE I											
STA. 65+00 TO STA. 73+54 LT.						356		854			
STA. 65+32 TO STA. 73+68 (DBL. SOLID)							697		1672		
STA. 72+20 TO STA. 73+68 (DIAG.)							42		100		
STA. 64+70 TO STA. 73+54 RT.						369		886			
STAGE II											
STA. 65+00 TO STA. 73+87 LT.						373		895			
STA. 64+20 TO STA. 73+87 (DBL. SOLID)							808		1940		
STA. 64+20 TO STA. 65+24 (DIAG.)							29		70		
STA. 72+74 TO STA. 73+87 (DIAG.)							37		90		
STA. 65+29.2 TO STA. 73+87 RT.						358		858			
STA. 10+25 (TEAL DRIVE)						9				20	
SUB-TOTAL		416	633			2124	1613	3493	3872	20	
TOTAL			1049		1580		3737		7365		20

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS.
 * 10% OF TOTAL LENGTH FOR SHORT-TERM PAVEMENT MARKING

PERMANENT SEEDING SCHEDULE

LOCATION	SEEDING CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	ACRE	POUND	POUND	POUND	TON	ACRE	POUND
STA. 59+44 TO STA. 65+00 LT	0.2	18	18	18	0.4	0.2	20
STA. 65+00 TO STA. 67+50 LT	0.2	18	18	18	0.4	0.2	20
STA. 69+00 TO STA. 70+42 LT	0.1	9	9	9	0.2	0.1	10
STA. 70+75 TO STA. 72+50 LT	0.1	9	9	9	0.2	0.1	10
STA. 66+03 TO STA. 67+95 RT	0.1	9	9	9	0.2	0.1	10
STA. 69+41 TO STA. 73+00 RT	0.3	27	27	27	0.6	0.3	30
TOTAL	1.0	90	90	90	2.0	1.0	100

SCHEDULE TRENCH BACKFILL

LOCATION	QUANTITY
	CU YD
STA. 65+48.2 TO STA. 65+48.9 RT.	1.0
STA. 70+41.7 TO STA. 70+43.7 LT.	16.9
STA. 70+43.7 TO STA. 70+73.7 LT.	7.8
STA. 70+39.6 TO STA. 70+39.8 RT.	28.9
STA. 71+48.9 TO STA. 71+10.2 RT.	72.2
TOTAL	127

SCHEDULE PERIMETER EROSION BARRIER

LOCATION	QUANTITY
	FOOT
STA. 65+00 TO STA. 67+50 LT.	250
STA. 66+10 TO STA. 68+00 RT.	194
STA. 68+92 TO STA. 70+30 LT.	138
STA. 69+20 TO STA. 72+91 RT.	390
STA. 70+89 TO STA. 72+00 LT.	130
TOTAL	1102

SCHEDULE SUB-BASE GRANULAR MATERIAL TYPE A

LOCATION	QUANTITY
	TON
STA. 65+00 TO STA. 65+58.5 RT	31
STA. 66+02 TO STA. 67+72 RT	162
STA. 67+04 TO STA. 67+36 LT	24
STA. 67+31 TO STA. 67+44 (C)	49
STA. 67+44 TO STA. 67+48.6 (C)	13
STA. 67+60.1 TO STA. 67+74.9	104
STA. 69+24.7 TO STA. 69+39.5	105
STA. 69+47.6 TO STA. 69+52.2 (C)	13
STA. 69+52.2 TO STA. 69+66 (C)	52
STA. 69+24.1 TO STA. 70+43 LT	98
STA. 69+60.5 TO STA. 72+61 RT	233
TOTAL	884

SCHEDULE AGGREGATE (EROSION CONTROL)

LOCATION	QUANTITY
	TON
STA. 67+00 LT & RT	10
STA. 69+00 LT	5
STA. 69+31 RT	5
STA. 70+50 RT	5
TOTAL	25

SCHEDULE PAVEMENT REMOVAL

LOCATION	PAVEMENT REMOVAL	APPR SLAB REMOVAL	PVMT REM (SPECIAL)
	SQ YD	SQ YD	SQ YD
STA. 67+31 TO STA. 67+37.04 (C)	29.6		
STA. 67+37.04 TO STA. 67+80 LT	42.8		
STA. 67+37.04 TO STA. 67+87.04 (C)		133.5	
STA. 67+37.04 TO STA. 68+00 RT	68.2		
STA. 68+97 TO STA. 69+58.96 LT	63.9		
STA. 69+08.96 TO STA. 69+58.96 (C)		133.5	
STA. 69+16 TO STA. 69+58.96 RT	45.8		
STA. 69+58.96 TO STA. 69+66 (C)	34.8		
STA. 69+80 TO STA. 70+05 LT			11.5
STA. 71+30 TO STA. 71+55 LT			11.5
TOTAL	286	267	23

SCHEDULE STONE RIPRAP

LOCATION	STONE RIPRAP, CLASS A4	FILTER FABRIC
	SQ YD	SQ YD
STA. 66+50 TO STA. 67+94.6 RT (DITCH)	270	270
STA. 67+50 LT TO STA. 69+46 RT (BRIDGE)	2375	2375
TOTAL	2645	2645

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
STA. 59+50 TO STA. 66+50 LT	26	20	175	-155
STA. 66+50 TO STA. 67+50 LT	9	7	176	-169
STA. 69+00 TO STA. 72+50 LT	7	5	299	-294
STA. 66+20 TO STA. 68+00 RT	229	172	197	-25
STA. 69+50 TO STA. 73+00 RT	352	264	157	+107
TOTAL	623	468	1004	-536

GUTTER SCHEDULE

LOCATION	CONCRETE GUTTER TYPE B (SPECIAL)	GUTTER OUTLET	GUTTER OUTLET (SPECIAL)	GUTTER REMOVAL
	FOOT	EACH	FOOT	FOOT
STA. 66+03 TO STA. 66+54 RT.			62	
STA. 70+09 TO STA. 72+85 RT.				76
STA. 70+11 TO STA. 70+45 LT.				69
STA. 70+73 TO STA. 72+50 LT.	211			213
STA. 70+40 TO STA. 70+44 LT.	31			
STA. 72+49 TO STA. 72+85 RT.		1		
TOTAL	242	1	62	358

COMBINATION CURB & GUTTER SCHEDULE

LOCATION	COMBINATION CONCRETE CURB & GUTTER, TYPE B - 6.18'	COMBINATION CURB AND GUTTER REMOVAL	COMBINATION CONCRETE CURB & GUTTER (SPECIAL)
	FOOT	FOOT	FOOT
STA. 65+00 TO STA. 65+57 RT.	84		
STA. 65+17.3 TO STA. 65+58.7 RT.		72	
STA. 65+73.4 TO STA. 65+82.6 RT.		42	15
TOTAL	84	114	15

SCHEDULE TREE REMOVAL

LOCATION	ACRES	(OVER 15 UNITS DIAMETER) UNIT
	ACRE	UNIT
STA. 67+70 75' LT. TO STA. 68+10 79.7' LT.	0.01	
STA. 68+90 60' RT. TO STA. 69+20 100' RT.	0.01	
STA. 60+05, 64' LT		16
TOTAL	0.1	16

SCHEDULE INLET AND PIPE PROTECTION

LOCATION	QUANTITY
	EACH
STA. 65+48.2 RT	1
STA. 65+48.9 RT	1
STA. 65+50 LT	1
STA. 70+39.6 RT	1
STA. 70+41.7 LT	1
STA. 70+43.7 LT	1
STA. 70+73.7 LT	1
STA. 70+84.6 LT	1
STA. 71+48.9 RT	1
TOTAL	9

SCHEDULE PAVED DITCH REMOVAL

LOCATION	QUANTITY
	FOOT
STA. 66+01 TO STA. 66+30 RT	44
TOTAL	44

SCHEDULE PAVED SHOULDER REMOVAL

LOCATION	QUANTITY
	SQ YD
STA. 65+00 TO STA. 65+17.3 RT	17
TOTAL	17

FILE NAME = D672A73-sh-t-schedule.dgn

USER NAME = laughlin1
 DESIGNED -
 DRAWN -
 PLOT SCALE = 2.0000' / IN.
 CHECKED -
 PLOT DATE = Jun-28-2010 10:57:53AM
 DATE -

REVISOR -
 REVISIONS -
 REVISIONS -
 REVISIONS -
 REVISIONS -



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL
 62708 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

QUANTITY SCHEDULES

SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 662 SECTION HRS-10,B-2) COUNTY SANGAMON TOTAL SHEETS 84 SHEET NO. 15 CONTRACT NO. 72A73 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT