


SUMMARY OF QUANTITIES				ROADWAY FAP 662 80% FEDERAL 20% STATE	STRUCTURE S.N. 084-0521 80% FEDERAL 20% STATE	PPP RESURFACING 80% FED. 20% STATE FAP 662	SIDEWALK 80% STATE 20% VILLAGE
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				I000-2A	X071-2A	I000-2A	SFTY-1B
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	23467			23467	
44000400	GUTTER REMOVAL	FOOT	358	358			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	114	114			
44000600	SIDEWALK REMOVAL	SQ FT	91				91
40004552	APPROACH SLAB REMOVAL	SQ YD	267	267			
44004000	PAVED DITCH REMOVAL	FOOT	44	44			
44004250	PAVED SHOULDER REMOVAL	SQ YD	17	17			
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	23	23			
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	235			235	
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	235			235	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	235			235	
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	235			235	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50104650	SLOPE WALL REMOVAL	SQ YD	418		418		
50200100	STRUCTURE EXCAVATION	CU YD	278		278		
50300100	FLOOR DRAINS	EACH	14		14		
50300225	CONCRETE STRUCTURES	CU YD	286.7		286.7		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	589.2		589.2		
50300260	BRIDGE DECK GROOVING	SQ YD	1324		1324		
50300280	CONCRETE ENCASEMENT	CU YD	18.2		18.2		
50300300	PROTECTIVE COAT	SQ YD	1773		1773		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6060		6060		
50500505	STUD SHEAR CONNECTORS	EACH	7140		7140		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	172190		172190		
50800515	BAR SPLICERS	EACH	848		848		
50901720	BICYCLE RAILING	FOOT	384		384		
50901750	PARAPET RAILING	FOOT	384		384		
51201400	FURNISHING STEEL PILES HP 10x42	FOOT	1362		1362		
51202305	DRIVING PILES	FOOT	550		550		
51203400	TEST PILE STEEL HP 10x42	EACH	2		2		
51204650	PILE SHOES	EACH	52		52		

USER NAME = laughlin1
 PLOT SCALE = 10.0000' / IN.
 PLOT DATE = Jun-28-2010 10:44:15AM

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL.
 62703 Phone: (217)544-8033 IL. Design Firm
 No. 184-001907

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	HRS-10,B-2)	SANGAMON	84	4
CONTRACT NO. 72A73				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				