

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGED CONSTRUCTION				
LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATION	ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
BKEABUT	69261.75	-1.75	510.00	510.00
CLBRGE	69264.92	-1.75	510.01	510.01
A	69274.92	-1.75	510.04	510.08
B	69284.92	-1.75	510.08	510.13
C	69294.92	-1.75	510.12	510.19
D	69304.92	-1.75	510.17	510.24
E	69314.92	-1.75	510.23	510.28
F	69324.92	-1.75	510.29	510.32
G	69334.92	-1.75	510.35	510.37
CLP1	69343.75	-1.75	510.42	510.42
H	69353.75	-1.75	510.50	510.50
J	69363.75	-1.75	510.58	510.60
K	69373.75	-1.75	510.67	510.71
L	69383.75	-1.75	510.77	510.82
M	69393.75	-1.75	510.86	510.92
N	69403.75	-1.75	510.96	511.01
P	69413.75	-1.75	511.05	511.09
Q	69423.75	-1.75	511.15	511.17
R	69433.75	-1.75	511.25	511.25
CLP2	69440.09	-1.75	511.31	511.31
S	69450.09	-1.75	511.40	511.41
T	69460.09	-1.75	511.50	511.53
U	69470.09	-1.75	511.59	511.64
V	69480.09	-1.75	511.69	511.75
W	69490.09	-1.75	511.79	511.85
X	69500.09	-1.75	511.88	511.93
Y	69510.09	-1.75	511.98	512.00
CLP3U1	69518.92	-1.75	512.06	512.06
CLP3	69520.00	-1.75	512.07	512.07

PGL				
LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATION	ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
BKEABUT	69261.75	0.00	510.03	510.03
CLBRGE	69264.92	0.00	510.04	510.04
A	69274.92	0.00	510.07	510.10
B	69284.92	0.00	510.11	510.16
C	69294.92	0.00	510.15	510.21
D	69304.92	0.00	510.20	510.26
E	69314.92	0.00	510.25	510.30
F	69324.92	0.00	510.31	510.34
G	69334.92	0.00	510.38	510.39
CLP1	69343.75	0.00	510.45	510.45
H	69353.75	0.00	510.52	510.53
J	69363.75	0.00	510.61	510.63
K	69373.75	0.00	510.70	510.74
L	69383.75	0.00	510.79	510.85
M	69393.75	0.00	510.89	510.95
N	69403.75	0.00	510.99	511.04
P	69413.75	0.00	511.08	511.12
Q	69423.75	0.00	511.18	511.20
R	69433.75	0.00	511.27	511.28
CLP2	69440.09	0.00	511.33	511.33
S	69450.09	0.00	511.43	511.44
T	69460.09	0.00	511.53	511.55
U	69470.09	0.00	511.62	511.67
V	69480.09	0.00	511.72	511.78
W	69490.09	0.00	511.81	511.88
X	69500.09	0.00	511.91	511.96
Y	69510.09	0.00	512.00	512.03
CLP3U1	69518.92	0.00	512.09	512.09
CLP3	69520.00	0.00	512.10	512.10

GIRDER 4				
LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATION	ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
BKEABUT	69261.75	3.29	509.98	509.98
CLBRGE	69264.92	3.29	509.99	509.99
A	69274.92	3.29	510.02	510.05
B	69284.92	3.29	510.05	510.11
C	69294.92	3.29	510.10	510.16
D	69304.92	3.29	510.15	510.21
E	69314.92	3.29	510.20	510.25
F	69324.92	3.29	510.26	510.29
G	69334.92	3.29	510.33	510.34
CLP1	69343.75	3.29	510.39	510.39
H	69353.75	3.29	510.47	510.48
J	69363.75	3.29	510.56	510.58
K	69373.75	3.29	510.65	510.69
L	69383.75	3.29	510.74	510.80
M	69393.75	3.29	510.84	510.90
N	69403.75	3.29	510.93	510.99
P	69413.75	3.29	511.03	511.07
Q	69423.75	3.29	511.13	511.15
R	69433.75	3.29	511.22	511.23
CLP2	69440.09	3.29	511.28	511.28
S	69450.09	3.29	511.38	511.39
T	69460.09	3.29	511.47	511.50
U	69470.09	3.29	511.57	511.62
V	69480.09	3.29	511.67	511.73
W	69490.09	3.29	511.76	511.82
X	69500.09	3.29	511.86	511.91
Y	69510.09	3.29	511.95	511.98
CLP3U1	69518.92	3.29	512.04	512.04
CLP3	69520.00	3.29	512.05	512.05

DESIGNED -	J.M.B.
CHECKED -	T.E.S.
DRAWN -	R KING
CHECKED -	J.M.B.

HOMER L. CHASTAIN & ASSOCIATES, LLP
CONSULTING ENGINEERS
DECATUR (217) 422-8544
CHICAGO (773) 714-0050
ROCKFORD (815) 489-0050
184-001397

**DECK ELEVATIONS - UNIT 1
STRUCTURE NUMBER 059-0510**

SHEET NO. 8 OF 51 SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	761	107B-2	MACOUPIN	98	38
FAP ROUTE 761 (IL RT 108)			CONTRACT NO. 72A94		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			