

IL RTE 108 ROADWAY 80% FEDERAL 20% STATE	SN 059-0510 BRIDGE 80% FEDERAL 20% STATE
---	---

PAY CODE	ITEM	UNITS	TOTAL QUANTITY	CONSTRUCTION CODE TYPES	
				1000	X071-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	100	100	
20100500	TREE REMOVAL, ACRES	ACRE	0.44	0.44	
20200100	EARTH EXCAVATION	CU YD	888	888	
20300100	CHANNEL EXCAVATION	CU YD	2,394	2,394	
20400800	FURNISHED EXCAVATION	CU YD	2,784	2,784	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	154		154
25000200	SEEDING, CLASS 2	ACRE	2	2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180	180	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180	180	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180	180	
25100115	MULCH, METHOD 2	ACRE	2	2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	189	189	
28000315	AGGREGATE DITCH CHECKS	TON	355	355	
28000400	PERIMETER EROSION BARRIER	FOOT	1,407	1,407	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1205		1205
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	308	308	
28200200	FILTER FABRIC	SQ YD	1,821	308	1513
35101400	AGGREGATE BASE COURSE, TYPE B	TON	30	30	
35650500	BASE COURSE WIDENING 10"	SQ YD	484	484	

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
c:\pwork\PW1007\LAUGHLINRL\0212999	72A94-Sht-500.dgn	DRAWN -	REVISED -
PLOT SCALE = 40.0000 ' / IN.		CHECKED -	REVISED -
PLOT DATE = Jun-28-2010 01:38:46PM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.P. RTE. 761	SECTION 107B-2	COUNTY MACOUPIN	TOTAL SHEETS 98	SHEET NO. 3
CONTRACT NO. 72A94				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

Rev.