

PAY CODE	ITEM	UNITS	TOTAL QUANTITY	IL RTE 108	SN 059-0510
				ROADWAY	BRIDGE
				80% FEDERAL	80% FEDERAL
				20% STATE	20% STATE
				CONSTRUCTION CODE TYPES	
				I000	X071-2A
50300280	CONCRETE ENCASEMENT	CU YD	18.4		18.4
50300300	PROTECTIVE COAT	SQ YD	3,036		3,036
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	6,588		6,588
50800105	REINFORCEMENT BARS	POUND	45	45	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	244,300		244,300
50800515	BAR SPLICERS	EACH	2,233		2,233
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1,792		1,792
51201610	FURNISHING STEEL PILES HP12X63	FOOT	3,144		3,144
51202305	DRIVING PILES	FOOT	4,936		4,936
51203600	TEST PILE STEEL HP12X53	EACH	2		2
51203610	TEST PILE STEEL HP12X63	EACH	4		4
51204650	PILE SHOES	EACH	48		48
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	114		114
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24
52100520	ANCHOR BOLTS, 1"	EACH	48		48
52100530	ANCHOR BOLTS, 1 1/4"	EACH	12		12
52100540	ANCHOR BOLTS, 1 1/2"	EACH	36		36
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	15	15	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	35	35	

FILE NAME =	USER NAME = leughl@r1	DESIGNED -	REVISED -
ct:\pvc_work\PIV1001\LAUGHLIN\ld0212999\2A94-Sht-S00.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Jun-20-2010 01:36:50PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 761	SECTION 107B-2	COUNTY MACOUPIN	TOTAL SHEETS 98	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72A94	

Rev.