

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				(25-3) I-6			(25-3HB-2) B
				90% FED. 10% STATE ROADWAY J000-2A	90% FEDERAL 8% STATE 2% CITY BIKE PATH & SIDEWALK J000-2A	100% CITY TRAFFIC SIGNALS PREEMPTORS Y031-3D	90% FED. 10% STATE BRIDGE X271-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	105	105			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	445	445			
20200100	EARTH EXCAVATION	CU YD	52390	52370	20		
20400800	FURNISHED EXCAVATION	CU YD	19860	19830	30		
X2090210	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	384				384
20800150	TRENCH BACKFILL	CU YD	88	79	9		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	72465	72339	126		
25000200	SEEDING, CLASS 2	ACRE	25	25			
25000300	SEEDING, CLASS 3	ACRE	1	1			
25000350	SEEDING, CLASS 7	ACRE	26	26			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2340	2340			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2340	2340			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2340	2340			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2	2			
A 25000750	MOWING	ACRE	26	26			
25100115	MULCH, METHOD 2	ACRE	26	26			
25100630	EROSION CONTROL BLANKET	SQ YD	1284	1284			
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	9	9			
28000305	TEMPORARY DITCH CHECKS	FOOT	1629	1611	18		
28000400	PERIMETER EROSION BARRIER	FOOT	7044	7044			
28000500	INLET AND PIPE PROTECTION	EACH	80	78	2		
28001000	AGGREGATE (EROSION CONTROL)	TON	4	4			
28100105	STONE RIPRAP, CLASS A3	SQ YD	105	105			
28100107	STONE RIPRAP, CLASS A4	SQ YD	202	202			
28200200	FILTER FABRIC	SQ YD	202	202			
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	38665	38665			
30200950	PROCESSING MODIFIED SOIL 18"	SQ YD	1978	1978			
30201500	LIME	TON	1050	1050			
31200500	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 4"	SQ YD	37427	37427			
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	2220	25	2203		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2395	192	2203		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	500	500			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	23	23			
40600300	AGGREGATE (PRIME COAT)	TON	1	1			
40603350	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	29	29			
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	184	184			
40800030	AGGREGATE (PRIME COAT)	TON	3	3			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1079	1079			
A 42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	21416	21416			
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	10264	10264			
42000540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	11264	11264			
42001200	PAVEMENT FABRIC	SQ YD	11869	11869			
42001300	PROTECTIVE COAT	SQ YD	52575	52476	99		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1337	1337			

A - Non-participating Specialty Items

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				(25-3) I-6			(25-3HB-2) B
				90% FED. 10% STATE ROADWAY J000-2A	90% FEDERAL 8% STATE 2% CITY BIKE PATH & SIDEWALK J000-2A	100% CITY TRAFFIC SIGNALS PREEMPTORS Y031-3D	90% FED. 10% STATE BRIDGE X271-2A
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	605	605			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	23639	6579	17060		
42400800	DETECTABLE WARNINGS	SQ FT	120	40	80		
44000100	PAVEMENT REMOVAL	SQ YD	31379	31379			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	292	292			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	761	761			
44000400	GUTTER REMOVAL	FOOT	81	81			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8865	8865			
X0004552	APPROACH SLAB REMOVAL	SQ YD	461	461			
X4402805	ISLAND REMOVAL	SQ FT	271	271			
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	367	367			
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	17342	17342			
44004000	PAVED DITCH REMOVAL	FOOT	249	249			
44004250	PAVED SHOULDER REMOVAL	SQ YD	14727	14727			
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	5240	5240			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	70		70		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1241	1241			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	203	203			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1
50104400	CONCRETE HEADWALL REMOVAL	EACH	11	11			
50104650	SLOPE WALL REMOVAL	SQ YD	747	747			
50105220	PIPE CULVERT REMOVAL	FOOT	408	408			
50157300	PROTECTIVE SHIELD	SQ YD	1155				1155
50200100	STRUCTURE EXCAVATION	CU YD	864				864
50300100	FLOOR DRAINS	EACH	12				12
50300225	CONCRETE STRUCTURES	CU YD	394.4				394.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	982.9				982.9
50300260	BRIDGE DECK GROOVING	SQ YD	2342				2342
50300280	CONCRETE ENCASMENT	CU YD	12				12
50300300	PROTECTIVE COAT	SQ YD	2943				2943
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1
50500505	STUD SHEAR CONNECTORS	EACH	7740				7740
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	283365				283365
50800515	BAR SPLICERS	EACH	2308				2308
50901730	BRIDGE FENCE RAILING	FOOT	257				257
51100100	SLOPE WALL 4 INCH	SQ YD	898				898
51201610	FURNISHING STEEL PILES HP12X63	FOOT	2084				2084
51202305	DRIVING PILES	FOOT	2084				2084
51203610	TEST PILE STEEL HP12X63	EACH	6				6
51204650	PILE SHOES	EACH	56				56
X0026407	TEMPORARY SHEET PILING	SQ FT	1429				1429
51500100	NAME PLATES	EACH	1				1
52100520	ANCHOR BOLTS, 1"	EACH	40				40
52100530	ANCHOR BOLTS, 1 1/4"	EACH	20				20

A Rev. 8-31-10