PAVING SCHEDULE

LOCATION STATION TO STATION	ROADWAY	PROCESSING MODIFIED SOIL 12" (SQ YD)	PROCESSING MODIFIED SOIL 18" (SQ YD)	LIME (TON)	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 4" (SQ YD)	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED) (SQ YD)	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED) (SQ YD)	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) (SQ YD)	AGGREGATE SHOULDERS TYPE B 6" (SQ YD)	SHOULDER RUMBLE STRIP (FT)	PROTECTIVE COAT (SQ YD)
36+78.21 TO 37+85.10	FAYETTE	82		2	76	46					46
37+85.10 TO 41+50.00	FAYETTE	2657		67	2404	1940					1940
41+50.00 TO 47+56.16	FAYETTE	5624		142	4730	4086					4086
47+56.16 TO 48+56.16	FAYETTE	846		21	766			668			668
51+50.79 TO 52+50.79	FAYETTE	846		21	766			669			669
52+50.79 TO 57+00.00	FAYETTE	4247		107	3619	3151					3151
57+00.00 TO 60+00.00	FAYETTE	2708		68	2118	1773					1773
60+00.00 TO 66+00.00	FAYETTE	4731		119	4139	3452					3452
66+00.00 TO 72+00.00	FAYETTE	4545		115	4478	4133					4133
72+00.00 TO 73+81.75	FAYETTE	1377		35	1357	1252					1252
7+39.97 TO 8+84.46	S. FRONTAGE RD	82		2	77	47					47
8+84.46 TO 9+64.00	S. FRONTAGE RD	770		20	768	758					758
0+26.00 TO 1+23.75	ILLINI DRIVE	803		20	797	778					778
12+40.00 TO 22+33.18	RAMP A	3629		92	3638		3288		354	1587	3288
10+47.73 TO 13+15.00	RAMP B	1001		25	1000		916		98	437	916
11+00.00 TO 20+95.97	RAMP C	1737	1978	119	3716		3370		419	1884	3370
10+47.73 TO 19+27.63	RAMP D	2980		75	2978		2690		370	1665	2690
	TOTAL	38665	1978	1050	37427	21416	10264	1337	1241	5573	33017*

*NOT A TOTAL QUANTITY

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION (CU YD)	FOR INFORMATION ONLY: EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25% (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	EXCESS EXCAVATION (CU YD)	FURNISHED EXCAVATION (CU YD)	REMARKS
PRE-STAGE 1							
FAYETTE AVE	199	149	516	-367	0	367	
RAMP C	48	37	488	-452	0	452	
CONNECTOR E	4	3	465	-462	0	462	
I-57/70	580	436	1411	-975	0	975	
SUBTOTAL PRE-STAGE 1	831	625	2881	-2256	0	2256	
STAGE 1							
FAYETTE AVE	3226	2419	10240	-7821	0	539	OBTAIN: 3959 CY FROM RAMP C, 2537 CY FROM RAMP D INFIELD, 326 CY FROM SO. FRONTAGE RD, 460 CY FROM CONNECTOR C1
RAMP C	5990	4493	249	4244	0	0	PLACE EXCESS AS EMBANKMENT: 3959 CY ON FAYETTE AVE STAGE 1, 285 CY ON CONNECTOR B1
RAMP D	4103	3078	5530	-2452	0	0	OBTAIN 2452 CY FROM RAMP D INFIELD GRADING STAGE 1
RAMP D INFIELD GRADING	6653	4990	1	4989	0	0	PLACE EXCESS AS EMBANKMENT: 2452 CY ON RAMP D, 2537 CY ON FAYETTE AVE STAGE 1
CONNECTOR B1	1	1	286	-285	0	0	OBTAIN: 285 CY FROM RAMP C
CONNECTOR C1	1596	1197	737	460	0	0	PLACE EXCESS AS EMBANKMENT: 460 CY ON FAYETTE AVE.
I-57/70	882	662	853	-192	0	192	
SOUTH FRONTAGE RD	443	333	6	326	0	0	PLACE EXCESS AS EMBANKMENT: 326 CY ON FAYETTE AVE STAGE 1
SUBTOTAL STAGE 1	22894	17172	17902	-731	0	731	
STAGE 1B							
FAYETTE AVE	78	59	238	-179	0	134	OBTAIN 45 CY FROM SO FRONTAGE RD
RAMP C	4995	3746	636	3111	0	0	PLACE EXCESS AS EMBANKMENT: 1120 CY ON RAMP B STAGE 2, 1991 CY ON FAYETTE AVE STAGE 2
SOUTH FRONTAGE RD	65	49	4	45	0	0	PLACE EXCESS AS EMBANKMENT: 45 CY ON FAYETTE AVE
SUBTOTAL STAGE 1B	5138	3854	877	2977	0	134	
PRE-STAGE 2							
I57/70	8	6	24	-18	0	18	
SUBTOTAL PRE-STAGE2	8	6	24	-18	0	18	
STAGE 2							
FAYETTE AVE	3937	2953	10702	-7749	0	2186	OBTAIN: 1991 CY FROM RAMP C STAGE 1B, 353 CY FROM CONNECTOR C1 REMOVAL, 3197 CY FROM RAMP C INFIELD GRADING
RAMP A	1179	884	15476	-14592	0	11432	OBTAIN: 2819 CY FROM RAMP A INFIELD, 341 CY FROM CONNECTOR E
RAMP A INFIELD GRADING	7647	5735	2917	2819	0	0	PLACE EXCESS AS EMBANKMENT: 2819 CY ON RAMP A STAGE 2
RAMP A OUTFIELD GRADING	1602	1202	5562	-4360	0	2882	OBTAIN: 178 CY FROM FAYETTE AVE STAGE 3, 214 CY FROM CONNECTOR B1 REMOVAL STAGE 3, 1086 CY FROM RAMP B OUTFIELD STAGE 3
RAMP B	336	252	2474	-2222	0	0	OBTAIN: 1120 CY FROM RAMP C STAGE 1B, 1086 CY FROM RAMP B INFIELD, 16 CY FROM ILLINI DRIVE
CONNECTOR E REMOVAL	464	348	7	341	0	0	PLACE EXCESS AS EMBANKMENT: 341 CY ON RAMP A
BIKE TRAIL	18	13	44	-30	0	30	
ILLINI DRIVE	36	27	11	16	0	0	PLACE EXCESS AS EMBANKMENT: 16 CY ON RAMP A
SUBTOTAL STAGE 2	15218	11415	37192	-25777	0	16530	
STAGE 2B							
FAYETTE AVE	658	494	780	-287	0	190	OBTAIN: 97 CY FROM ILLINI DRIVE
ILLINI DRIVE	139	104	7	97	0	0	PLACE EXCESS AS EMBANKMENT: 97 CY ON FAYETTE AVE
RAMP C OUTFIELD GRADING	4426	3320	122	3197	0	0	PLACE EXCESS AS EMBANKMENT: 3541 CY ON FAYETTE AVE STAGE 2
CONNECTOR C1 REMOVAL	505	379	26	353	0	0	PLACE EXCESS AS EMBANKMENT: 353 CY ON FAYETTE AVE STAGE 2
SUBTOTAL STAGE 2B	5728	4297	936	3360	0	190	
STAGE 3							
FAYETTE AVE	837	628	450	178	0	0	PLACE EXCESS AS EMBANKMENT: 178 CY ON RAMP A OUTFIELD STAGE 2
CONNECTOR B1 REMOVAL	286	214	1	214	0	0	PLACE EXCESS AS EMBANKMENT: 214 CY ON RAMP A OUTFIELD STAGE 2
RAMP B OUTFIELD GRADING	1448	1086	0	1086	0	0	PLACE EXCESS AS EMBANKMENT: 1086 CY ON RAMP A OUTFIELD STAGE 2
SUBTOTAL STAGE 3	2571	1928	451	1478	0	0	
SUBTOTAL	52388	39297	60263	-20967	0	19859	
PAY TOTAL	52390	39300	60265	-20970	0	19860	

NOTE: END AREAS FOR FAYETTE AVE, RAMP A, RAMP B, RAMP C, I-57/70, ILLINI DR, SO. FRONTAGE RD, BIKE TRAIL, AND RAMP CONNECTORS CAN BE FOUND ON THE MAINTENANCE OF TRAFFIC CROSS SECTION SHEETS. END AREAS FOR RAMP D AND INFIELD/OUTFIELD GRADING CAN BE FOUND ON THE RAMP D AND INFIELD/OUTFIELD CROSS SECTION SHEETS.

REMOVAL SCHEDULE

LOCATION STATION TO STATION	PAVEMENT REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	GUTTER REMOVAL (FOOT)	COMBINATION CURB & GUTTER REMOVAL (FOOT)	APPROACH SLAB REMOVAL (SQ YD)	ISLAND REMOVAL (SQ FT)	MEDIAN SURFACE REMOVAL (SQ FT)	PAVED DITCH REMOVAL (FOOT)	PAVED SHOULDER REMOVAL (SQ YD)
FAYETTE AVE										
36+78.27 TO 75+26.30	18533		761		6830	461		17342	95	3180
EX. FAYETTE RAMP A										
0+20.67 TO 11+40.00	1900				279		271			1110
EX. FAYETTE RAMP B										
4+93.00 TO 11+75.53	965				460					459
EX. FAYETTE RAMP C										
0+16.92 TO 17+92.21	2763	292								1954
EX. FAYETTE RAMP D										
0+00.00 TO 10+45.06	1573									1105
EX. FAYETTE RAMP E										
0+00.00 TO 14+06.29	2322									1463
EX. FAYETTE RAMP F										
0+18.90 TO 2+67.52	598				434					72
EX. FAYETTE RAMP G										
0+00.00 TO 3+33.71	572				197					239
ILLINI DRIVE										
0+25.90 TO 1+57.46	687				265					
S. FRONTAGE ROAD										
7+34.04 TO 9+73.65	803				400					
I-57/70										
2134+98.39 TO 2162+00.07	663			81					154	5145
TOTAL	31379	292	761	81	8865	461	271	17342	249	14727

SEEDING SCHEDULE

LOCATION STATION TO STATION	TOPSOIL FURNISH AND PLACE (SQ YD)	SEEDING CLASS 2 (ACRE)	SEEDING CLASS 3 (ACRE)	SEEDING CLASS 7 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	AGRICULTURAL GROUND LIMESTONE (TON)	MOWING (ACRE)	MULCH METHOD 2 (ACRE)
FAYETTE	35631	6.78	0.22	7.76	630	630	630	0.44	7.00	7.00
RAMP A	12645	8.47		8.44	762.3	762.3	762.3		8.47	8.47
RAMP B	1914	0.92	0.03	1.01	85.5	85.5	85.5	0.06	0.95	0.95
RAMP C	10222	3.24		3.94	291.6	291.6	291.6		3.24	3.24
RAMP D	8972	3.05		3.28	274.5	274.5	274.5		3.05	3.05
EX RAMP E				0.14						
BIKE TRAIL	126	0.04		0.04	3.6	3.6	3.6		0.04	0.04
I-57/70	2044	2.22	0.51	1.16	245.7	245.7	245.7	1.02	2.73	2.73
ILLINI DRIVE	476	0.07		0.07	6.3	6.3	6.3		0.07	0.07
SOUTH FRONTAGE RD	435	0.14		0.14	12.6	12.6	12.6		0.14	0.14
SUBTOTAL	72465	24.93	0.76	25.98	2312.1	2312.1	2312.1	1.5	25.69	25.69
PAY TOTAL	72465	25.00	1.00	26.00	2340.0	2340.0	2340.0	2.0	26.00	26.00

BIKE TRAIL SCHEDULE

LOCATION STATION	SIDE	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH (SQ FT)	AGGREGATE SHOULDERS, TYPE B (TON)	AGGREGATE BASE COURSE, TYPE B, 8" (SQ YD)
BIKE TRAIL				
7+87.89 TO 11+50.00	LT/RT	3621	19	563
38+50.00 TO 49+04.22	LT/RT	10542	51	1640
TOTAL		14163*	70	2203*

*NOT A TOTAL QUANTITY

SLOPE WALL REMOVAL SCHEDULE

LOCATION	SIDE	SLOPE WALL REMOVAL (SQ YD)
FAYETTE AVE STRUCTURE	LT/RT	747
TOTAL		747

FILE NAME = S:\Projects\403-00072_57-70\dgn\Fayette\Addendum\schedules.dgn	USER NAME = linda	DESIGNED - ESW	REVISED - 08-02-10
		DRAWN - ESW	REVISED - 08-26-10
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - BRM	REVISED -
	PLOT DATE = 8/26/2010	DATE - 11-16-07	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES, FAYETTE AVENUE

SCALE: | SHEET NO. 1 OF 6 SHEETS | STA. | TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3)I-6	EFFINGHAM	839	31

CONTRACT NO. 74293

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT