

**SUMMARY OF QUANTITIES**

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				(25-3HB-2)B 90% FED. 10% STATE BRIDGE X271-2A
				(25-3)I-6				
				90% FED. 10% STATE ROADWAY J000-2A	90% FEDERAL 8% STATE 2% CITY BIKE PATH & SIDEWALK J000-2A	100% CITY TRAFFIC SIGNALS PREEMPTORS Y031-3D		
* 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	54	54				
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	40	40				
* 88600100	DETECTOR LOOP, TYPE I	FOOT	3839	3839				
* 88700200	LIGHT DETECTOR	EACH	10		10			
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	3		3			
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8				
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	4	4				
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1				
* 89502380	REMOVE EXISTING HANDHOLE	EACH	9	9				
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5	5				
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	44	44				
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2	2				
X0323644	PAVEMENT MARKING GROOVING	FOOT	26455	26455				
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	8				8	
X0325605	PAVEMENT MARKING GROOVING	SQ FT	790	790				
<del>X0101000</del>	<del>TRAFFIC CONTROL AND PROTECTION, (SPECIAL)</del>	L SUM	<del>1</del>	<del>1</del>				
X0358300	REMOVE AND RELAY END SECTIONS	EACH	1	1				
<del>X0636000</del>	<del>BRIDGE DRAINAGE SYSTEM</del>	L SUM	<del>1</del>				<del>1</del>	
X5041800	CONCRETE ANCHORS	EACH	16	16				
X5510100	STORM SEWER REMOVAL	FOOT	179	179				
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	25	25				
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1				
* X7800605	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	790	790				
* X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	18791	18437	354			
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	4197	4197				
* X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	605	605				
* X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	2848	2848				
* X7800680	URETHANE PAVEMENT MARKING - LINE 24"	FOOT	370	370				
* X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1	1				
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2089	2089				
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	2249		2249			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0022800	FENCE REMOVAL	FOOT	1327	1327				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6				
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4				
⊙ Z0076600	TRAINEES	HOUR	1000	1000				
* A2C05065	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 5-GALLON	EACH	2	2				
* A2C07063	TREE, TAXODIUM DISTICHUM (BALD CYPRESS), CONTAINER GROWN, 3-GALLON	EACH	2	2				
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8	8				
* B2001464	TREE, CORNUS MAS (CORNELIAN CHERRY DOG WOOD), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	8	8				

© YOBO \* SPECIALTY ITEMS

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				(25-3HB-2)B 90% FED. 10% STATE BRIDGE X271-2A
				(25-3)I-6				
				90% FED. 10% STATE ROADWAY J000-2A	90% FEDERAL 8% STATE 2% CITY BIKE PATH & SIDEWALK J000-2A	100% CITY TRAFFIC SIGNALS PREEMPTORS Y031-3D		
* B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8	8				
Z0018800	DRAINAGE SYSTEM	L SUM	1				1	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	687				687	
X5080600	MECHANICAL SPLICERS	EACH	482				482	
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1				1	

Rev.