

PAVEMENT MARKING SCHEDULE

LOCATION	URETHANE PAVEMENT MARKING - LINE 4"		URETHANE PAVEMENT MARKING - LINE 6"	URETHANE PAVEMENT MARKING - LINE 8"	URETHANE PAVEMENT MARKING - LINE 12"		URETHANE PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	PAVEMENT MARKING GROOVING (FOOT)	PAVEMENT MARKING GROOVING (SQ FT)
	SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)					
FAYETTE AVE												
35+21 TO 76+47	8773		3811		158	129	239	281	11	602.4	13110.0	602.4
FAYETTE RAMP A												
16+00 TO 22+29	590	549	127	220		464	31	7		93.6	1980.0	93.6
FAYETTE RAMP B												
10+49 TO 13+00	191	190				515					897.0	
FAYETTE RAMP C												
9+52 TO 21+04	1094	1079	162	195		273	32	16		93.6	2835.0	93.6
FAYETTE RAMP D												
11+08 TO 21+09	823	968				184					1975.0	
ILLINI DRIVE												
0+26 TO 1+37	177		36	105		242	35				594.0	
S. FRONTAGE ROAD												
8+84 TO 9+64	125		61	85		39	33				343.0	
BIKE TRAIL												
7+88 TO 11+50	90											
38+50 TO 49+04	264											
I-57/70												
2134+98 TO 2158+82		3878				844					4721.0	
SUBTOTAL	12127	6664	4197	605	158	2690	370	304	11	789.6	26455.0	790
TOTAL	18791		4197	605	2848		370	304	11	790	26455	790

TREE REMOVAL SCHEDULE

LOCATION	STATION	SIDE	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
			(UNIT)	(UNIT)
FAYETTE AVE				
43+88	RT		6	16
44+24	RT		14	
44+25	RT			
44+30	RT			16
44+33	LT			22
45+08	LT		10	
46+83	RT			16
51+00	RT			31
51+03	LT			18
51+55	RT			28
52+35	LT			16
55+04	RT		14	
55+28	RT			16
EXISTING RAMP A				
9+13	RT		10	
9+44	RT		13	
10+88	RT		9	
11+36	RT		7	
PROPOSED RAMP A				
18+94	LT			18
19+65	LT		10	
20+08	LT		6	
20+09	LT			27
21+12	LT			60
PROPOSED RAMP D				
11+26	LT			36
11+31	LT		6	
11+43	LT			44
11+60	LT			37
11+86	LT			28
11+86	LT			16
TOTAL			105	445

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4"		TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 12"		TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
		SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	
FAYETTE AVE									
35+20.97 TO 76+47.18	602.4	8773		3811		158	129	239	6197
FAYETTE RAMP A									
16+00.00 TO 22+29.32	93.6	590	549	127	220		464	31	1208
FAYETTE RAMP B									
10+48.93 TO 13+15.00		191	190				515		642
FAYETTE RAMP C									
9+51.54 TO 21+04.15	93.6	1094	1079	162	195		273	32	1366
FAYETTE RAMP D									
11+07.97 TO 21+09.47		823	968				184		781
ILLINI DRIVE									
0+25.90 TO 1+37.46	177		36	105		242	35		458
S. FRONTAGE ROAD									
8+84.46 TO 9+63.90	125		61	85		39	33		235
BIKE TRAIL									
7+10.56 TO 11+50.00									
38+50.00 TO 49+04.22									
I-57/70									
2134+99.10 TO 2158+82.00		3878					844		2136
SUBTOTAL	789.6	11773	6664	4197	605	158	2690	370	13023
TOTAL	790	18437		4197	605	2848		370	13023

TRAFFIC CONTROL SCHEDULE

LOCATION	ROADWAY	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
STA 47+68 TO STA 52+38	FAYETTE	412.5	400	2	2
STA 2145+65 TO STA 2147+69	I-57/70 WB (LT)	137.5	175	1	1
STA 2145+72 TO STA 2147+77	I-57/70 WB (RT)	175		1	
STA 2145+08 TO STA 2147+11	I-57/70 EB (LT)	175		1	
STA 2145+14 TO STA 2147+18	I-57/70 EB (RT)	175.0	175	1	1
PAY TOTAL		1075	750	6	4

MOT AND MISCELLANEOUS PAVEMENT SCHEDULE

LOCATION	ROADWAY	AGGREGATE BASE COURSE, TYPE B 8" (SQ YD)	INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	PORTLAND CEMENT CONCRETE PAVEMENT 12" (SQ YD)	PAVEMENT FABRIC (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	AGGREGATE (PRIME COAT) (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105 (TON)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	PROTECTIVE COAT (SQ YD)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ YD)	MEDIAN REMOVAL PARTIAL DEPTH (SQ FT)	PAVEMENT REMOVAL (SPECIAL) (SQ YD)
38+57.70 TO 68+45.29	FAYETTE AVE	167	1076	2614	2614				175	3	2614			2614
0+36.44 TO 0+70.23	ILLINI DRIVE												97	
9+22.47 TO 9+67.25	SO. FRONTAGE RD												270	
14+14.14 TO 15+19.96	RAMP A CONNECTOR			216	216									
13+15.00 TO 14+15.75	RAMP B CONNECTOR			139	139									
0+29.50 TO 1+62.14	TEMP RAMP B1			396	396									396
29+15.70 TO 34+74.69	TEMP RAMP C			658	658									658
0+57.49 TO 4+76.61	TEMP RAMP C1			905	905									905
9+50.47 TO 11+00.00	RAMP C						1	29				107		
18+00.00 TO 19+50.00	RAMP C			109	109									109
19+27.63 TO 20+77.29	RAMP D			345	345							96		
0+27.00 TO 11+98.63	TEMP RAMP E			765	765									558
2134+98.39 TO 2162+00.00	I-57/70			5117	5117									
TOTAL		167	1076*	11264	11264*	23	1	29	175*	3	11264*	203	367	5240

*NOT A TOTAL QUANTITY

FENCE SCHEDULE

LOCATION	STATION TO STATION	SIDE	CHAIN LINK FENCE, 6' (FOOT)	FENCE REMOVAL (FOOT)
11+43.94 TO 17+64.31		RT	613	626
13+00.19 TO 19+49.30		RT	626	701
TOTAL			1239	1327