


CONTROL POINT	STATION	OFFSETS TO LEFT EDGE			OFFSETS TO RIGHT EDGE		
		PAVEMENT	MEDIAN	ISLAND	ISLAND	MEDIAN	PAVEMENT
A ₂ B ₁	59+30.00	35.00		11.00	11.00		35.00
	59+55.00	34.63		10.63	11.00		35.00
	59+80.00	34.25		10.25	11.00		35.00
	60+05.00	33.88		9.88	11.00		35.00
	60+30.00	33.50		9.50	11.00		35.00
	60+55.00	33.13		9.13	11.00		35.00
	60+80.00	32.75		8.75	11.00		35.00
	61+05.00	32.38		8.38	11.00		35.00
	61+30.00	32.00		8.00	11.00		35.00
	61+55.00	31.63		7.63	11.00		35.00
B ₂	61+64.27	31.49		7.49	11.00		35.00
	61+80.00	31.26		7.24	11.00		35.00
	62+05.00	30.88		6.74	11.00		35.00
	62+30.00	30.51		6.14	11.00		35.00
	62+55.00	30.13		5.43	11.00		35.00
	62+80.00	29.76		4.62	11.00		35.00
C ₁	63+05.00	29.38		3.7	11.00		35.00
	63+17.80	29.19	5.19	3.19	11.00		35.00
B ₃ D ₁	63+30.00	29.01	5.01	2.68	11.00		35.00
	63+31.00	29.00	5.00	2.64	11.00		35.00
B ₄ B ₅	63+55.00	28.64	4.64	1.55	9.68		35.12
	63+80.00	28.26	4.26	0.31	8.31		35.24
	64+05.00	27.89	3.89	-1.03	6.93		35.37
	64+21.87	27.63	3.63	-2.00	6.00	6.00	35.45
A ₃ C ₂ C ₃ D ₂	64+30.00	27.51	3.51			5.56	35.49
	64+55.00	27.14	3.14			4.18	35.62
	64+80.00	26.76	2.76			2.81	35.74
	65+05.00	26.39	2.39			1.43	35.87
	65+30.00	26.01	2.01			0.06	35.99
	65+31.00	26.00	2.00			0.00	36.00

OFFSETS ARE FOR THE LANE OFFSETS RELATIVE TO THE CENTERLINE.



FILE NAME =	USER NAME = paul	DESIGNED - JWS	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CHANNELIZED APPROACHES, FAYETTE AVENUE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\Projects\403-00072.51-70\dm\Fayette\ccofayette.dgn	DRAWN - PDB	REVISOR -	57/70			(25-3)I-6	EFFINGHAM	839	185	
PLOT SCALE = 40.0000' / IN.	CHECKED - BRM	REVISOR -	CONTRACT NO. 74293							
PLOT DATE = 6/24/2010	DATE - 11-05-07	REVISOR -	ILLINOIS FED. AID PROJECT							
					SCALE: 1"=20'	SHEET NO. 4 OF 4 SHEETS		STA. 59+25.00 TO STA. 65+50.00		FED. ROAD DIST. NO.