



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 1, 2010

SUBJECT: FAI Route 55 (I-55)  
Project ACNHI-055-1 (084) 034  
Section 60-3 RS-1, 60-(3HB, 3HB-1)I  
Madison County  
Contract No. 76601  
Item No. 23, September 17, 2010 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised sheets 1, 5 and 6 of the Plans.
3. Added sheet 19D to the Plans.
4. Revised page iii of the Table of Contents to the Special Provisions.
5. Added page 208 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; R. E. Anderson;  
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON- -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XZ193500	BR DK MIC C OVL 2 1/4	SQ YD	4,064.000				
X0549200	CLEAN PAVED DITCH	FOOT	1,000.000				
X6320100	GUARDRAIL REMOV SPL	FOOT	2,339.000				
X7800200	PAINT PVT MARK CURB	FOOT	115.000				
X7830068	GRV RCSD PVT LT N SYM	SQ FT	472.000				
X7830074	GRV RCSD PVT MRKG 7	FOOT	2,042.000				
Z0004556	HMA SURFACE RM (DECK)	SQ YD	1,584.000				
Z0006204	BR DECK HY-SCAR 1/2	SQ YD	2,608.000				
Z0006225	BR DECK HY-SCAR 2 1/2	SQ YD	1,456.000				
Z0007101	C&D LEAD PT CL RS N1	L SUM	1.000				
Z0007102	C&D LEAD PT CL RS N2	L SUM	1.000				
Z0007103	C&D LEAD PT CL RS N3	L SUM	1.000				
Z0007104	C&D LEAD PT CL RS N4	L SUM	1.000				
Z0010501	CLEAN & PT STL BR N1	L SUM	1.000				
Z0010502	CLEAN & PT STL BR N2	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0010503	CLEAN & PT STL BR N3	L SUM	1.000				
Z0010504	CLEAN & PT STL BR N4	L SUM	1.000				
Z0012754	STR REP CON DP = < 5	SQ FT	561.000				
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	18.000				
Z0016702	DETOUR SIGNING	L SUM	1.000				
Z0026346	NIGHT WORK ZONE LIGHT	L SUM	1.000				
* Z0030150	IMPACT ATTEN NRD TL3	EACH	6.000				
* Z0030350	IMP ATTN REL NRD TL3	EACH	6.000				
Z0040530	PIPE UNDERDRAIN REMOV	FOOT	114,268.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0075310	TIE BARS 3/4	EACH	28.000				
Z0076600	TRAINEES	HOUR	2,500.000		0.800		2,000.000
20200100	EARTH EXCAVATION	CU YD	544.000				
20400800	FURNISHED EXCAVATION	CU YD	100.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	1,632.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)I

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000210	SEEDING CL 2A	ACRE	0.240				
25000400	NITROGEN FERT NUTR	POUND	21.600				
25000500	PHOSPHORUS FERT NUTR	POUND	21.600				
25000600	POTASSIUM FERT NUTR	POUND	21.600				
25100105	MULCH METHOD 1	ACRE	0.240				
28000520	ABOVE GRADE INLT FLTR	EACH	7.000				
28100101	STONE RIPRAP CL A1	SQ YD	26.000				
35101100	AGG BASE CSE A 12	SQ YD	1,632.000				
40600200	BIT MATLS PR CT	TON	128.500				
40600300	AGG PR CT	TON	618.000				
40600982	HMA SURF REM BUTT JT	SQ YD	1,525.000				
40600985	PCC SURF REM BUTT JT	SQ YD	854.000				
40600990	TEMPORARY RAMP	SQ YD	950.000				
40603153	P HMA SC SMA N80	TON	17,683.000				
40603240	P HMA BC IL19.0 N90	TON	19,627.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42100360	CONT REINF PCC PVT 13	SQ YD	1,451.000				
42100615	PAVT REINFORCEMENT	SQ YD	1,451.000				
42101300	PROTECTIVE COAT	SQ YD	1,451.000				
44000100	PAVEMENT REM	SQ YD	1,451.000				
44000162	HMA SURF REM 3 1/4	SQ YD	147,894.000				
44000198	HMA SURF REM VAR DP	SQ YD	93,516.000				
44004250	PAVED SHLD REMOVAL	SQ YD	2,933.000				
44200577	CL A PATCH T2 12	SQ YD	301.000				
44200581	CL A PATCH T3 12	SQ YD	84.000				
44200583	CL A PATCH T4 12	SQ YD	84.000				
44200934	CL B PATCH T2 8	SQ YD	461.000				
44213000	PATCH REINFORCEMENT	SQ YD	916.000				
44213200	SAW CUTS	FOOT	5,863.000				
44300200	STRIP REF CR CON TR	FOOT	2,971.000				
48101200	AGGREGATE SHLDS B	TON	124.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON - -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)I

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48102100	AGG WEDGE SHLD TYPE B	TON	5,282.000				
48203033	HMA SHOULDERS 9	SQ YD	2,933.000				
48203100	HMA SHOULDERS	TON	16,926.000				
50102400	CONC REM	CU YD	59.600				
50104000	BRIDGE RAIL REMOVAL	FOOT	1,968.000				
50104650	SLOPE WALL REMOV	SQ YD	32.000				
50157300	PROTECTIVE SHIELD	SQ YD	1,413.000				
50300225	CONC STRUCT	CU YD	18.800				
50300255	CONC SUP-STR	CU YD	107.500				
50300260	BR DECK GROOVING	SQ YD	3,878.000				
50300300	PROTECTIVE COAT	SQ YD	5,743.000				
50500405	F & E STRUCT STEEL	POUND	8,610.000				
50500715	JACK & REM EX BEARING	EACH	52.000				
50800205	REINF BARS, EPOXY CTD	POUND	23,970.000				
50800515	BAR SPLICERS	EACH	72.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52000110	PREF JT STRIP SEAL	FOOT	434.000				
52100010	ELAST BEARING ASSY T1	EACH	47.000				
52100020	ELAST BEARING ASSY T2	EACH	5.000				
52100520	ANCHOR BOLTS 1	EACH	104.000				
58700300	CONCRETE SEALER	SQ FT	1,196.000				
60100060	CONC HDWL FOR P DRAIN	EACH	236.000				
60100078	SHOULDER RM&RPL 12.5	FOOT	100,425.000				
60100945	PIPE DRAINS 12	FOOT	12.000				
60107600	PIPE UNDERDRAINS 4	FOOT	107,424.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	6,844.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	4,650.000				
63100045	TRAF BAR TERM T2	EACH	8.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100089	TRAF BAR TERM T6B	EACH	8.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	20.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63400105	GUARD POSTS	EACH	7.000				
63500105	DELINEATORS	EACH	312.000				
63500120	DELINEATOR REMOVAL	EACH	312.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	103,961.000				
66500105	WOV W FENCE 4	FOOT	1,000.000				
66502300	WOV W FENCE REMOV	FOOT	1,000.000				
67000400	ENGR FIELD OFFICE A	CAL MO	24.000				
67100100	MOBILIZATION	L SUM	1.000				
* 70100207	TRAF CONT-PROT 701402	EACH	6.000				
70100420	TRAF CONT-PROT 701411	EACH	4.000				
70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
* 70106700	TEMP RUMBLE STRIP	EACH	12.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	36.000				
70300100	SHORT-TERM PAVT MKING	FOOT	13,176.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)I

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300220	TEMP PVT MK LINE 4	FOOT	10,295.000				
70300240	TEMP PVT MK LINE 6	FOOT	122,018.000				
70300250	TEMP PVT MK LINE 8	FOOT	4,099.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	1,464.000				
* 70400100	TEMP CONC BARRIER	FOOT	3,600.000				
* 70400200	REL TEMP CONC BARRIER	FOOT	3,600.000				
72000100	SIGN PANEL T1	SQ FT	395.000				
78000200	THPL PVT MK LINE 4	FOOT	10,295.000				
78000400	THPL PVT MK LINE 6	FOOT	106,496.000				
78000500	THPL PVT MK LINE 8	FOOT	4,099.000				
78001100	PT PVT MK LTRS & SYMB	SQ FT	472.000				
78001110	PAINT PVT MK LINE 4	FOOT	2,854.000				
78004230	PREF PL PM TB INL L6	FOOT	15,522.000				
78100100	RAISED REFL PAVT MKR	EACH	1,482.000				
78100105	RAISED REF PVT MKR BR	EACH	8.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76601

State Job # - C-98-106-10  
 PPS NBR - 8-85402-0000  
 County Name - MADISON - -  
 Code - 119 - -  
 District - 8 - -  
 Section Number - 60-3RS-1,60-(3HB,3HB-1)I

Project Number  
 ACNHI-0551/084/034

Route  
 FAI 55

\* REVISED : SEPTEMBER 1, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78200300	PRISMATIC CURB REFL	EACH	24.000				
78200410	GUARDRAIL MKR TYPE A	EACH	89.000				
78200530	BAR WALL MKR TYPE C	EACH	24.000				
78201000	TERMINAL MARKER - DA	EACH	20.000				
78300200	RAISED REF PVT MK REM	EACH	1,490.000				
80300110	LOC UNDERGR CABLE SPL	EACH	20.000				

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 185  
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 185  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 187  
SURFACE TESTING OF PAVEMENTS (BDE) ..... 187  
THERMOPLASTIC PAVEMENT MARKINGS (BDE) ..... 193  
TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE) ..... 194  
TRAINING SPECIAL PROVISIONS ..... 194  
TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) ..... 196  
WORKING DAYS (BDE) ..... 197  
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) ..... 197  
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 200  
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 204  
TRAFFIC CONTROL AND PROTECTION, (SPECIAL) ..... 208

Revised 09/01/2010

**TRAFFIC CONTROL AND PROTECTION, (SPECIAL)**

This work shall be done according to Section 701 of the Standard Specifications and the Traffic Control Plan as shown in the plans and as specified within.

This item shall include all traffic control required for construction of structure number 060-0198 as shown on the construction staging and traffic control plans, except for traffic control and protection paid for separately.

This traffic control and protection will be paid for at the contract unit price per each for TRAFFIC CONTROL AND PROTECTION, (SPECIAL).

Added 09/01/2010