

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A			
				90% FED	90% FED	90% FED	90% FED	90% FED			
				10% STATE	10% STATE	10% STATE	10% STATE	10% STATE			
				ROADWAY	SN 060-0195 ALHAMBRA RD	SN 060-0198 NEW DOUGLAS	SN 060-0196 I-55 OVER RR	SN 060-0197 I-55 OVER RR			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3600	3240							
*72000100	SIGN PANEL - TYPE 1	SQ FT	395	395							
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10295	10295							
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	106496	106496							
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4099	4099							
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2854	2854							
*78001100	PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	472	472							
*78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	15522	15522							
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1482	1482							
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8							
*78200300	PRISMATIC CURB REFLECTOR	EACH	24	24							
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	89	89							
*78200530	BARRIER WALL MARKERS, TYPE C	EACH	24		8	8	4	4			
*78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	20	20							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1490	1490							
*80300110	LOCATING UNDERGROUND CABLE, SPECIAL	EACH	20	20							
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	561		95	430	18	18			
X0325605	PAVEMENT MARKING GROOVING	SQ FT	472	472							
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1							
NP X0549200	CLEANING PAVED DITCH	FOOT	1000	1000							
X6320100	GUARDRAIL REMOVAL SPECIAL	FOOT	2339	2339							
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	2042	2042							
*X7800200	PAINT PAVEMENT MARKING CURB	FOOT	115	115							
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	4064		1062	1546	728	728			
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	0	4							
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	2608		1062	1546					
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	0	4							
Z0006225	BRIDGE DECK HYDRO-SCARIFICATION 2 1/2"	SQ YD	1456				728	728			
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	18		14	4					
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	114268	114268							
Z0075310	TIE BARS 3/4"	EACH	28	28							
Z0048865	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				0.5	0.5			
Z0016702	DETOUR SIGNING	L SUM	1								
*X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	472	472							
0 Z0076600	TRAINEES	HOUR	2500	2500							

NP-NON-PARTICIPATING @Y080 *SPECIALTY ITEMS

Rev. 9-1-10 Rev.

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -
cs:\pw_work\PIWDOT\CONOVERPJ\d0128605\d076601-sht-plan.dgn	76601-sht-plan.dgn	DRAWN -	REVISED -
PLOT SCALE = 50.0000' / 1" IN.		CHECKED -	REVISED -
PLOT DATE = 6/24/2010		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60-3RS-1,60-(3HB,3HB-1)I	MADISON	123	6
CONTRACT NO. 76601				
ILLINOIS FED. AID PROJECT				