

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED. / 10% STATE	100% STATE	-----	CODE NO	ITEM	UNIT		90% FED. / 10% STATE	100% STATE	-----
			I000	Y002-1C					I000	Y002-1C			
72000100	SIGN PANEL - TYPE 1	SQ FT	280		280	X	80300100	LOCATING UNDERGROUND CABLE	FOOT	59598	59598		
72000200	SIGN PANEL - TYPE 2	SQ FT	21		21		X0301735	CONCRETE HEADWALL REPAIR	EACH	1	1		
72000300	SIGN PANEL - TYPE 3	SQ FT	4192		4192		X0322654	GRADE AND SHAPE MEDIAN DITCH CHECKS	EACH	6	6		
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	106	106			X0324743	SUBGRADE REINFORCEMENT	SQ YD	7978	7978		
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2310	2310			X0325420	INSTALL FURNISHED SIGNS	EACH	24	24		
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	696	696		X	X0325606	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	EACH	1	1		
73400100	CONCRETE FOUNDATIONS	CU YD	4.2	4.2		X	X0326677	REMOVE HIGH TENSION CABLE MEDIAN BARRIER	FOOT	57398	57398		
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	695	695		X	X0326687	REMOVE HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	18	18		
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	5627	5627		X	Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	17604	17604			X0326692	MOTORIST AID CALL BOX REMOVAL	EACH	1	1		
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	269425	269425			X0976500	END SECTIONS TO BE REMOVED	EACH	8	8		
78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	8920	8920			X4421000	PARTIAL DEPTH PATCHING	TON	19	19		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3417	3417			X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	166	166		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12			X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	7888	7888		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	118	118			X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	5627	5627		
78200530	BARRIER WALL MARKERS, TYPE C	EACH	432	432			Z0012710	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	402	402		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	21	21			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	143546	143546			Z0014800	CULVERT TO BE CLEANED	FOOT	3285	3285		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3425	3425			Z0017202	DOWEL BARS 1 1/2"	EACH	1668	1668		
							Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	62	62		
							X	Z0029652	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	57438	57438	
							X	Z0029654	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	20	20	
							Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		

Δ Non-Participating
 * Specialty Items