

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	
LOCATION	EACH
RT., STA. 972+78	4
TOTAL =	4

CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"		
LOCATION	SKEW	EACH
LT., STA. 1244+90	30 LT. AHD.	1
TOTAL =		1

CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 54"	
LOCATION	EACH
IL 140	
871+61.26 LT	1
871+61.26 RT	1
TOTAL =	2

REINFORCED CONCRETE PIPE ELBOW 24"	
LOCATION	EACH
LT., STA. 999+77	2
LT., STA. 1006+75	2
TOTAL =	4

FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	
LOCATION	EACH
STA. 989+78	1
STA. 999+77	1
STA. 1006+75	1
STA. 1105+38	1
TOTAL =	4

INSERTION CULVERT LINER 12"	
LOCATION	FOOT
STA. 1165+46 TO STA. 1167+38	192
TOTAL =	192

INSERTION CULVERT LINER 36"	
LOCATION	FOOT
LT., STA. 1165+44 TO STA. 1166+58	114
RT., STA. 1166+20 TO STA. 1167+28	108
TOTAL =	222

CONTROLLED LOW-STRENGTH MATERIAL		
LOCATION	SIZE & TYPE	CU. YD.
STA. 1230+20	12" CMP	2.8
TOTAL =		2.8

PIPE DRAINS 12" (SPECIAL) CONCRETE THRUST BLOCKS CONCRETE HEADWALL FOR PIPE DRAINS				
LOCATION	SIZE	PIPE DRAIN EACH	THRUST BLK. EACH	CONC. HDW. EACH
LT., STA. 1001+14	12"	64	1	1
RT., STA. 1001+32	12"	72	1	1
RT., STA. 1004+85	12"	74	1	1
TOTAL =		210	3	3

FOR INFO

HEADWALL INCLUDED IN THE COST OF THE PIPE DRAIN 12" (SPECIAL)

MANHOLES, TYPE A, 5'-DIAMETER, WITH MEDIAN INLET (604106)	
LOCATION	EACH
STA. 1174+44	1
TOTAL =	1

INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	
LOCATION	EACH
STA. 1001+50	1
STA. 1004+45	1
TOTAL =	2

INLETS, TYPE B, WITH MEDIAN INLET (604106)	
LOCATION	EACH
STA. 983+42	1
TOTAL =	1

REMOVING INLETS	
LOCATION	EACH
STA. 983+42	1
STA. 989+78	1
STA. 999+77	1
STA. 1105+38	1
STA. 1174+44	1
TOTAL =	5

CONCRETE HEADWALL REPAIR	
LOCATION	EACH
LT., STA. 798+90	1
TOTAL =	1

END SECTIONS TO BE REMOVED		
LOCATION	SIZE & TYPE	EACH
LT., STA. 741+25	24" CONC.	1
RT., STA. 741+70	24" CONC.	1
LT., STA. 1089+98	24" CONC.	1
LT., STA. 1168+00	24" CONC.	1
LT., STA. 1186+00	24" CONC.	1
LT., STA. 1194+00	24" CONC.	1
RT., STA. 1253+65	24" CONC.	1
RAMP 1 (IL 140)		
LT., STA. 103+00	24" CONC.	1
TOTAL =		8

GRADE AND SHAPE MEDIAN DITCH CHECKS	
LOCATION	EACH
RT., STA. 669+00	1
LT., STA. 696+70	1
STA. 735+00	1
STA. 989+75	1
STA. 999+70	1
STA. 1006+85	1
TOTAL =	6

PAVEMENT REMOVAL	
LOCATION	SQ. YD.
I-55 NB STA. 734+00 TO STA. 743+00	2400
I-55 SB STA. 734+00 TO STA. 743+00	2400
I-55 NB STA. 1114+80 TO STA. 1121+00	1653
I-55 SB STA. 1114+80 TO STA. 1121+00	1653
TOTAL =	8,106

TEMPORARY SHEET PILING	
LOCATION	SQ. FT.
STA. 734+50	694
TOTAL =	694

BOX CULVERT END SECTIONS	
LOCATION	EACH
STA. 734+50	2
TOTAL =	2

PRECAST CONCRETE BOX CULVERT 8' X 3'	
LOCATION	FOOT
STA. 734+50	148
TOTAL =	148